

| | | | | |
|---------------------------|---------|----------|------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 22 | * | FULTON | 71 | 5 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |
| * 133RS-3;134RS-2;135RS-5 | | | | |

SUMMARY OF QUANTITIES

CONSTR. CODE
100% FEDERAL

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY 1000 RURAL |
|------------|-----------------------------------------------------|--------|----------------|--------------------------|
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 1681 | 1681 |
| 48203029 | HOT-MIX ASPHALT SHOULDERS, 8" | SQ YD | 4937 | 4937 |
| 50104400 | CONCRETE HEADWALL REMOVAL | EACH | 1 | 1 |
| 54215577 | METAL END SECTIONS 42" | EACH | 2 | 2 |
| 54248515 | CONCRETE COLLAR | EACH | 2 | 2 |
| 54390230 | INSERTION CULVERT LINER 36" | FOOT | 55 | 55 |
| * 63000001 | STEEL PLATE BEAM GUARD RAIL, TYPE A, 6' FOOT Posts | FOOT | 4275 | 4275 |
| * 63000025 | STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES | FOOT | 100 | 100 |
| * 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 15 | 15 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 3150 | 3150 |
| 66700205 | PERMANENT SURVEY MARKERS, TYPE I | EACH | 1 | 1 |
| 66700605 | PERMANENT SURVEY TIES | EACH | 4 | 4 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 4 | 4 |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 | 1 |
| 70100600 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336 | L SUM | 1 | 1 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 7615 | 7615 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 110360 | 110360 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1269 | 1269 |
| * 78005110 | EPOXY PAVEMENT MARKING - LINE 4" | FOOT | 110360 | 110360 |

* SPECIALTY ITEM

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DRAWN BY _____
CHECKED BY _____