

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	*	FULTON	71	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 133RS-3;134RS-2;135RS-5				

# SCHEDULE OF QUANTITIES

20200500

EARTH EXCAVATION (WIDENING)	UNIT
LOCATION	CU YD
IL 78: RT Sta. 239+30 TO 261+79	111.62
IL 78: RT Sta. 298+52 TO 314+86.50	81.12
IL 78: RT Sta. 315+63 TO 322+59	34.54
IL 78: LT Sta. 315+64 TO 322+73.50	35.21
IL 78: RT Sta. 323+41.50 TO 338+45	74.62
IL 78: LT Sta. 323+26 TO 351+59.84	140.64
IL 78: RT Sta. 339+55.50 TO 351+59.84	59.77
IL 78: RT Sta. 102+23.63 TO 123+75.70	106.81
IL 78: LT Sta. 102+23.63 TO 109+96.50	38.36
IL 78: LT Sta. 110+83.50 TO 123+76.30	64.16
IL 78: RT Sta. 124+40.30 TO 160+25	177.92
IL 78: LT Sta. 124+39.75 TO 160+25	177.93
<b>TOTAL</b>	<b>1,103 CU YD</b>

28000720

MULCH, METHOD 2	UNIT
LOCATION	ACRE
IL 78: RT Sta. 315+44	0.05
<b>TOTAL</b>	<b>0.05 ACRE</b>

40600895

CONSTRUCTING TEST STRIP	UNIT
LOCATION	EACH
JOBSITE	1
<b>TOTAL</b>	<b>1 EACH</b>

44000400

GUTTER REMOVAL	UNIT
LOCATION	FOOT
IL 78: RT Sta. 241+00 TO 241+83	83
IL 78: RT Sta. 308+00 TO 313+00	500
<b>TOTAL</b>	<b>583 FT</b>

44201803

CLASS D PATCHES, TYPE II, 13 INCH	UNIT
LOCATION	SQ YD
IL 78: Sta. 27+09 TO 36+67	30
IL 78: Sta. 36+67 TO 78+80	51
IL 78: Sta. 78+80 TO 127+41	53
IL 78: Sta. 127+41 TO 185+40	69
IL 78: Sta. 185+40 TO 251+62	88
IL 78: Sta. 251+62 TO 315+25	243
IL 78: Sta. 315+25 TO 330+48	27
IL 78: Sta. 330+48 TO 124+08	54
IL 78: Sta. 124+08 TO 160+25	49
<b>TOTAL</b>	<b>664 SQ YD</b>

44201807

CLASS D PATCHES, TYPE III, 13 INCH	UNIT
LOCATION	SQ YD
IL 78: Sta. 27+09 TO 36+67	33
IL 78: Sta. 36+67 TO 78+80	34
IL 78: Sta. 127+41 TO 185+40	16
IL 78: Sta. 185+40 TO 251+62	101
IL 78: Sta. 251+62 TO 315+25	96
IL 78: Sta. 315+25 TO 330+48	32
IL 78: Sta. 330+48 TO 124+08	36
<b>TOTAL</b>	<b>348 SQ YD</b>

44201809

CLASS D PATCHES, TYPE IV, 13 INCH	UNIT
LOCATION	SQ YD
IL 78: Sta. 27+09 TO 36+67	.36
IL 78: Sta. 36+67 TO 78+80	55
IL 78: Sta. 127+41 TO 185+40	101
IL 78: Sta. 185+40 TO 251+62	163
<b>TOTAL</b>	<b>355 SQ YD</b>

54248515

CONCRETE COLLAR	UNIT
LOCATION	EACH
IL 78: RT Sta. 315+44	2
<b>TOTAL</b>	<b>2 EACH</b>

54390230

INSERTION CULVERT LINER 36"	UNIT
LOCATION	FOOT
IL 78: RT Sta. 315+44	55
<b>TOTAL</b>	<b>55 FT</b>

63000001

STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	UNIT
LOCATION	FOOT
IL 78: RT Sta. 261+22.5 TO 266+35	512.5
IL 78: LT Sta. 261+97.5 TO 266+35	437.5
IL 78: RT Sta. 267+65.5 TO 272+78	512.5
IL 78: RT Sta. 267+65.5 TO 272+78	512.5
IL 78: LT Sta. 305+54.5 TO 309+42	387.5
IL 78: RT Sta. 306+87.5 TO 309+43.75	256.25
IL 78: LT Sta. 309+79.5 TO 314+04.5	425
IL 78: RT Sta. 309+81.25 TO 314+31.25	450
IL 78: RT Sta. 314+43.75 TO 315+35	106.25
IL 78: RT Sta. 328+12.5 TO 331+50	337.5
IL 78: LT Sta. 329+22.5 TO 332+60	337.5
<b>TOTAL</b>	<b>4,275 FT</b>

63000025

STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	UNIT
LOCATION	FOOT
IL 78: RT Sta. 309+43.75 TO 309+81.25	37.5
IL 78: LT Sta. 309+42 TO 309+79.5	37.5
IL 78: RT Sta. 314+31.25 TO 314+43.75	12.5
IL 78: LT Sta. 314+04.5 TO 314+17	12.5
<b>TOTAL</b>	<b>100 FT</b>

63000025

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	UNIT
LOCATION	EACH
IL 78: RT Sta. 260+72.5 TO 261+22.5	1
IL 78: LT Sta. 261+47.5 TO 261+97.5	1
IL 78: RT Sta. 266+35 TO 266+85	1
IL 78: LT Sta. 266+35 TO 266+85	1
IL 78: RT Sta. 267+15.5 TO 267+65.5	1
IL 78: LT Sta. 267+15.5 TO 267+65.5	1
IL 78: RT Sta. 272+78 TO 273+28	1
IL 78: LT Sta. 272+78 TO 273+28	1
IL 78: LT Sta. 305+04.5 TO 305+54.5	1
IL 78: RT Sta. 306+37.5 TO 306+87.5	1
IL 78: LT Sta. 314+17 TO 314+67	1
IL 78: RT Sta. 327+62.5 TO 328+12.5	1
IL 78: LT Sta. 328+72.5 TO 329+22.5	1
IL 78: RT Sta. 331+50 TO 332+00	1
IL 78: LT Sta. 332+60 TO 333+10	1
<b>TOTAL</b>	<b>15 EACH</b>

63200310

GUARDRAIL REMOVAL	UNIT
LOCATION	FOOT
IL 78: LT Sta. 263+47.5 TO 266+85	337.5
IL 78: RT Sta. 262+72.5 TO 266+85	412.5
IL 78: LT Sta. 267+15.5 TO 271+78	462.5
IL 78: RT Sta. 267+15.5 TO 271+90.5	475
IL 78: LT Sta. 306+75 TO 310+25	350
IL 78: RT Sta. 308+75 TO 310+25	150
IL 78: LT Sta. 313+00 TO 314+62.5	162.5
IL 78: RT Sta. 313+75 TO 315+46.5	200
IL 78: LT Sta. 329+20 TO 332+20	300
IL 78: RT Sta. 328+70 TO 331+70	300
<b>TOTAL</b>	<b>3,150 FT</b>

67000400

ENGINEER'S FIELD OFFICE, TYPE A	UNIT
LOCATION	CAL MO
JOBSITE	4
<b>TOTAL</b>	<b>4 CAL MO</b>

67100100

MOBILIZATION	UNIT
LOCATION	L SUM
JOBSITE	1
<b>TOTAL</b>	<b>1 L SUM</b>

70100460

TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	UNIT
LOCATION	L SUM
JOBSITE	1
<b>TOTAL</b>	<b>1 L SUM</b>

70100500

TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	UNIT
LOCATION	L SUM
JOBSITE	1
<b>TOTAL</b>	<b>1 L SUM</b>

70100600

TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	UNIT
LOCATION	L SUM
JOBSITE	1
<b>TOTAL</b>	<b>1 L SUM</b>

70102620

TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	UNIT
LOCATION	L SUM
JOBSITE	1
<b>TOTAL</b>	<b>1 L SUM</b>

78200410

GUARDRAIL MARKERS, TYPE A	UNIT
LOCATION	EACH
IL 78: RT Sta. 261+97.5 TO 266+35	5
IL 78: LT Sta. 262+72.5 TO 266+35	4
IL 78: RT Sta. 267+65.5 TO 271+40.5	4
IL 78: LT Sta. 267+65.5 TO 271+28	4
IL 78: LT Sta. 305+54.5 TO 314+17	10
IL 78: RT Sta. 306+87.5 TO 315+35	10
IL 78: LT Sta. 329+20 TO 332+20	4
IL 78: RT Sta. 328+70 TO 331+70	4
<b>TOTAL</b>	<b>45 EACH</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY