

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	*	FULTON	71	24
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 133RS-3;134RS-2;135RS-5				

# SCHEDULE OF QUANTITIES

## TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	HMA SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL 0.75 IN	HMA SURFACE REMOVAL 2 IN	HMA SURFACE REMOVAL (VAR DEPTH)	POLY BIT MATERIALS PRIME COAT	AGGREGATE MATERIALS PRIME COAT	HMA SURF CSE MIX "D" N 50	INCIDENTAL HMA SURFACING	AGGREGATE SHOULDERS TYPE B			
													LEFT AREA	LEFT SIDE	RIGHT AREA	RIGHT SIDE
													SQ YD	TON	SQ YD	TON
S. Norris Rd.			433.83	76.11	13.33	433.83			0.17	0.87		48.59			19.00	1.35
E. Brereton Rd.			150.00	60.00	14.44	150.00			0.06	0.30		16.80	8.33	0.59		
W. Brereton Rd.			129.17	51.67	12.78	129.17			0.05	0.26		14.47			8.33	0.59
<b>Entrances and Turnouts</b>																
5 Commercial Entrances			139.11			139.11			0.06	0.28		15.58				
42 Private Ent./Mailbox Turnouts			1032.20			1032.20			0.41	2.06		115.61				
<b>SUB-TOTAL</b>				187.78	40.55	1,884.31			0.75	3.77		211.04	8.33	0.59	27.33	1.95
<b>SUB-TOTAL (FROM SHEET 21 )</b>				1,265.28	329.43	91,610.06	11,788.26	1,706.67	42.39	211.95	11,678.51	269.54		838.29		839.93
<b>GRAND-TOTAL</b>				<b>1,453</b>	<b>370</b>	<b>93,494</b>	<b>11,788</b>	<b>1,707</b>	<b>43</b>	<b>216</b>	<b>11,679</b>	<b>481</b>		<b>839</b>		<b>842</b>

SURFACE TYPE	BIT PR COAT (GAL/SQ YD)	AGG PR COAT (LB/SQ YD)
COLD MILLED SURFACES	0.1	4
EXISTING PAVEMENT	0.05	4
NEW BITUMINOUS COURSES	0.03	2

SURFACE TYPE	
BIT. SURF. COURSES	112 LB /SQ YD/IN
ALL OTHER BIT.	112 LB /SQ YD/IN
AGGREGATE SHOULDERS	2.05 TONS/CUYD

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES

SCALE: VERT. DATE      HORIZ. DATE      DRAWN BY      CHECKED BY