

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	131RS-4	PEORIA	17	8
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	HMA SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL 0.5 IN	POLY BIT MATERIALS PRIME COAT	AGGREGATE MATERIALS PRIME COAT	P LEVELING BINDER (MM) IL 4.75 ,N50 0.75 IN	HMA SURF CSE MIX D,N50 1.5 IN	INCIDENTAL HMA SURFACING	AGGREGATE SHOULDERS TYPE B (WEDGE)	
												LEFT SIDE	RIGHT SIDE
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	TON	TON
STA. 1067 + 70 TO 1068 + 00	24.00	30.00	80.00	80.00	28.89		0.04	0.16		6.72		0.57	0.57
STA. 1068 + 00 TO 1226 + 50	24.00	15850.00	42266.67			42266.67	21.98	84.53	1791.92	3550.40		604.0	604.0
STA. 1226 + 50 TO 1226 + 80	24.00	30.00	80.00	80.00	28.89		0.04	0.16		6.72		0.57	0.57
Sideroads													
Shissler Road													
STA. 1090 + 00 Rt.		26.00	150.22	150.22	23.33		0.08	0.30			16.82		
STA. 1090 + 00 Lt.		100.00	903.86	83.30	24.44	820.56	0.47	1.81	34.46		75.92		
Claybaugh Road													
STA. 1143 + 79 Rt.		27.00	130.50	130.50	22.22		0.07	0.26			14.62		
STA. 1143 + 79 Lt.		26.00	132.89	132.89	24.44		0.07	0.27			14.88		
Rosenbohm Road													
STA. 1170 + 38 Rt.		25.00	123.61	123.61	21.11		0.06	0.25			13.84		
STA. 1170 + 38 Lt.		30.00	138.33	138.33	20.00		0.07	0.28			15.49		
Gerber Road													
STA. 1222 + 49 Rt.		51.00	410.83	410.83	27.78		0.21	0.82			46.01		
Route 8													
STA. 1222 + 49 Lt.		138.00	1999.30	103.30	30.00	1896.00	1.04	4.00	79.63		167.94		
Driveways													
STA. 1083 + 00 Lt. MB Turnout		72.00	40.89			40.89	0.02		1.72		3.43		
STA. 1083 + 70 Lt.		19.00	49.60	49.60			0.03	0.10			5.56		
STA. 1114 + 68 Rt.		23.00	71.60	71.60			0.04	0.14			8.02		
STA. 1115 + 44 Rt. MB Turnout		72.00	40.89			40.89	0.02		1.72		3.43		
STA. 1165 + 52 Rt.		20.00	81.10	81.10			0.04	0.16			9.08		
STA. 1213 + 19 Lt.		20.00	38.90	38.90			0.02	0.08			4.36		
STA. 1213 + 10 Rt. MB Turnout		72.00	40.89			40.89	0.02		1.72		3.43		
STA. 1213 + 32 Rt.		20.00	105.60	105.60			0.05	0.21			11.83		
STA. 1213 + 73 Lt.		20.00	51.10	51.10			0.03	0.10			5.72		
STA. 1214 + 64 Lt.		15.00	41.70	41.70			0.02	0.08			4.67		
GRAND-TOTAL				1,872.58	251.1	45,105.9	24.4	93.7	1,911.2	3,563.8	425.2	605	605
											TOTAL	1210	

SURFACE TYPE	P BIT PR COAT (GAL/SQ YD)	AGG PR COAT (LB/SQ YD)
COLD MILLED SURFACES	0.1	4
EXISTING PAVEMENT	0.05	4
NEW HOT-MIX ASPHALT COURSES	0.03	2

SURFACE TYPE	
HMA SURF. COURSES	112 LB /SQ YD/IN
ALL OTHER HMA	112 LB /SQ YD/IN
AGGREGATE SHOULDERS	2.05 TONS/CUYD

SCHEDULE OF QUANTITIES