

SUMMARY OF QUANTITIES

CODE NO.	ITEM CONSTRUCTION CODE	UNIT	TOTAL QUANTITY	FAP 323 (US 36) PIATT CO. STA. 759+39 TO STA.765+84 (BK)	FAP 323 (US 36) DOUGLAS CO. STA. 0+00 TO STA. 116+88.50	FAP 323 (US 36) DOUGLAS CO. BRIDGE S.N. 021-0016
				RURAL 100% FED I000	RURAL 100% FED I000	RURAL 100% FED X020-2A
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	18197.0	290.0	17907.0	
40600300	AGGREGATE (PRIME COAT)	TON	364.0	6.0	358.0	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	6102.0	105.0	5997.0	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2127.0	100.0	2027.0	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1372.0	0.0	1372.0	
40600990	TEMPORARY RAMP	SQ YD	6988.0	100.0	6888.0	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	8758.0	210.0	8538.0	10.0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3497.0	0.0	3497.0	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1439.0	9.0	1430.0	
40800030	AGGREGATE (PRIME COAT)	TON	29.0	1.0	28.0	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1210.0	7.0	1203.0	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	139042.0	2392.0	136650.0	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	4515.0	0.0	4403.0	112.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	13017.0	82.0	12935.0	
44201835	CLASS D PATCHES, TYPE I, 16 INCH	SQ YD	11.0	0.0	11.0	
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	947.0	0.0	947.0	
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	224.0	0.0	224.0	
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SQ YD	129.0	0.0	129.0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2826.0	35.0	2791.0	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3032.0	34.0	2998.0	
48203105	HOT-MIX ASPHALT SHOULDER SPECIAL	TON	86.0	0.0	86.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0	0.0	4.0	
67100100	MOBILIZATION	L SUM	1.0	0.1	0.9	

*SPECIALTY ITEMS