

SUMMARY OF QUANTITIES

LOCATION OF WORK: FAP 709
 US 136
 RURAL TWO LANE
 CHAMPAIGN COUNTY
 STA 1924+00
 TO
 STA. 2127+75

FUNDING BREAKOUT: 100% FEDERAL

CONSTRUCTION TYPE CODE: 1000

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL.	11,800.0
40600300	AGGREGATE (PRIME COAT)	TON	120.0
40600625	LEVELING BINDER (MACHINE METHOD), N 50	TON	2,423.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600982	HMA SURFACE REMOVAL- BUTT JOINT	SQ YD	2,269.0
40600990	TEMPORARY RAMP	SQ YD	72.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N 50	TON	4,874.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GAL.	312.0
40800030	AGGREGATE (PRIME COAT)	TON	7.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	265.0
44000152	HOT-MIX ASPHALT SURFACE REMOVAL 3/4"	SQ YD	57,690.0
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	959.0
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	138.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,665.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	164.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL. MO.	3.0
67100100	MOBILIZATION	L. SUM	1.0
70100450	TRAFFIC CONTROL & PROTECTION STANDARD 701201	L. SUM	1.0
70100460	TRAFFIC CONTROL & PROTECTION STANDARD 701306	L. SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,240.0
70300625	TEMPORARY PAINT PAVEMENT MARKING- LINE 4"	FOOT	44,430.0
70300660	TEMPORARY PAINT PAVEMENT MARKING- LINE 24"	FOOT	60.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	733.0
* 78001110	PAINT PAVEMENT MARKING- LINE 4"	FOOT	44,430.0
* 78001180	PAINT PAVEMENT MARKING- LINE 24"	FOOT	60.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	255.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	255.0
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	304.0
X4421000	PARTIAL DEPTH PATCHING	TON	94.0
XX005938	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	4.0

*** SPECIALTY ITEM**

FILE NAME #	USER NAME #	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pw_work\PIERSONBR\dms87996\070261.sht-S00.dgn	piersonbr	DRAWN -	REVISED -			709	105RS-2	Champaign	19	4
PLOT SCALE : 42.0/23 "/ IN.		CHECKED -	REVISED -			CONTRACT NO. 70261				
PLOT DATE : 2/6/2009		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT	