

SCHEDULE OF DRAINAGE STRUCTURES

STATION			#5000884 RE-ATTACH END SECTION EACH	54010305 PRC BOX CULV 3' X 5' FOOT	X0914260 PRC BOX CULV END SEC 3' X 5' EACH	50105210 REM EXST CULV FOOT	542D0217 PIPE CULV CL "D" TY 1 12" FOOT	542D0229 PIPE CULV CL "D" TY 1 24" FOOT	542A0229 PIPE CULV CL "A" TY 1 24" FOOT	54213669 PRC FLR END SEC 24" EACH	X0320547 REM AND REINSTALL END SEC 24" EACH	54213447 END SEC 12" EACH	50300225 CONCRETE STRUCTURES CU YD	50102400 CONCRETE REMOVAL CU YD	50800205 RE-BAR EPOXY COATED LBS
ROADWAY(S) A & D															
RDWY A	MED	621+00	1.0												
RDWY A	RT	721+07				20.0		20.0			1.0				
RDWY D	MED	648+30		10.0	1.0										
SUB-TOTAL =			1.0	10.0	1.0	20.0	0.0	20.0	0.0	0.0	1.0	0.0	0.0	0.0	0.0
ROADWAY G															
RDWY G	RT	633+35											2.2	2.2	118.0
SUB-TOTAL =			0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2.2	2.2	118.0
RDWY L VET NB & RDWY K VET SB															
RDWY L VET NB	RT	49+00					100.0					2.0			
RDWY L VET NB	RT	50+00				100.0									
RDWY L VET NB	LT	51+05				10.0		10.0			1.0	2.0			
RDWY L VET NB	RT	66+50							6.0	1.0					
RDWY K VET SB	RT	53+00				10.0		10.0			1.0				
RDWY K VET SB	RT	56+47				10.0		10.0			1.0				
RDWY K VET SB	RT	59+00				10.0		10.0			1.0				
SUB-TOTAL =			0.0	0.0	0.0	140.0	100.0	40.0	6.0	1.0	4.0	4.0	0.0	0.0	0.0
VETERANS PARKWAY RAMPS															
RAMP J	LT	3+00											1.0		
RAMP M	RT	37+50		30.0	1.0										
RAMP O	LT	21+50											1.0		
SUB-TOTAL =			0.0	30.0	1.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	2.0	0.0	0.0
TOTAL =			1.0	40.0	2.0	160.0	100.0	60.0	6.0	1.0	5.0	4.0	4.2	2.2	118.0