

48101200 AGGREGATE SHOULDERS, TYPE B

		STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ.YD)	SHOULDER THICKNESS (INCHES)	(TON)
ROADWAY(S) A & D									
RDWY A	LT	603+50.00		LT 606+50.00	300.0	4	133.3	1.75	12.6
RDWY D	LT	607+00.00		LT 610+90.00	390.0	2	86.7	1.75	8.2
RDWY A	LT	606+50.00		LT 608+50.00	200.0	4	88.9	1.75	8.4
RDWY A	LT	608+50.00		LT 718+77.72	11027.7	4	4901.2	1.75	464.6
RDWY A	RT	608+50.00		RT 636+00.00	2750.0	2	611.1	1.75	57.9
RDWY D	LT	610+90.00		LT 613+49.71	259.7	2	57.7	1.75	5.5
RDWY D	RT	610+90.00		RT 716+91.00	10601.0	4	4711.6	1.75	446.6
RDWY D	LT	624+94.00		LT 630+52.00	558.0	2	124.0	1.75	11.8
RDWY D	LT	636+99.97		LT 645+25.00	825.0	2	183.3	1.75	17.4
RDWY A	RT	642+82.00		RT 649+44.00	662.0	2	147.1	1.75	13.9
RDWY D	LT	652+05.00		LT 702+66.00	5061.0	2	1124.7	1.75	106.6
RDWY A	RT	658+96.30		RT 703+60.87	4464.6	2	992.1	1.75	94.0
RDWY D	LT	712+07.00		LT 713+36.55	129.6	2	28.8	1.75	2.7
RDWY A	RT	709+73.00		RT 716+91.00	718.0	2	159.6	1.75	15.1
RDWY A	LT	720+55.30		LT 737+00.00	1644.7	4	731.0	1.75	69.3
RDWY A	RT	726+92.27		RT 727+00.00	7.7	2	1.7	1.75	0.2
RDWY D	LT	722+21.97		LT 729+65.00	743.0	2	165.1	1.75	15.7
RDWY D	RT	720+52.36		RT 737+00.00	1647.6	4	732.3	1.75	69.4
RDWY A	RT	736+49.83		RT 737+00.00	50.2	2	11.1	1.75	1.1
SUB-TOTAL =									1421.1

ROADWAY G

RDWY G	LT	608+50.00		LT 642+00.00	3350.0	4	1488.9	1.75	141.1
RDWY G	RT	608+50.00		RT 642+00.00	3350.0	2	744.4	1.75	70.6
SUB-TOTAL =									211.7

RDWY L VET NB & RDWY K VET SB

RDWY K VET SB	RT	29+05.00		RT 30+00.00	95.0	4	42.2	1.75	4.0
RDWY L VET NB	RT	32+65.00		RT 51+90.34	1925.3	2	427.9	1.75	40.6
RDWY L VET NB	LT	32+65.00		LT 37+52.00	487.0	2	108.2	1.75	10.3
RDWY K VET SB	RT	37+31.00		RT 45+29.40	798.4	4	354.8	1.75	33.6
RDWY L VET NB	LT	47+66.00		LT 51+90.34	424.34	2	94.3	1.75	8.9
RDWY K VET SB	RT	53+03.64		RT 57+30.63	426.99	4	189.8	1.75	18.0
RDWY L VET NB	RT	53+39.73		RT 57+36.92	397.19	2	88.3	1.75	8.4
RDWY L VET NB	LT	61+10.00		LT 70+00.00	890	4	395.6	1.75	37.5
RDWY K VET SB	RT	62+48.37		RT 83+44.00	2095.6	3	748.4	1.75	70.9
RDWY K VET SB	LT	29+05.00		LT 51+48.41	2243.4	3	813.1	1.75	77.1
RDWY L VET NB	RT	58+81.64		RT 84+12.00	2530.4	3	930.5	1.75	88.2
RDWY K VET SB	LT	53+03.64		LT 57+30.63	427.0	3	159.3	1.75	15.1
RDWY K VET SB	LT	58+74.97		LT 83+44.00	2469.03	3	934.1	1.75	88.5
RDWY L VET NB	LT	76+50.00		LT 84+12.00	762	3	292.3	1.75	27.7
SUB-TOTAL =									528.8

(CONT'D NEXT SHEET)

SHEET 14 OF 22

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PIWIDOT\SHERRERJM\dms83233\70605 SCHEDULES OF QUANT.dgn	DRAWN - JMS	REVISED -	74			57-20(1)&(57-4,5,6)RS-3	MCLEAN	160	33	
PLOT SCALE = 40.0000' / IN.	CHECKED - JMS	REVISED -	CONTRACT NO. 70505							
PLOT DATE = 1/30/2009	DATE - 01-22-2009	REVISED -	SCALE: _____			SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT		