

SUMMARY OF QUANTITIES

100% FED

LOCATION OF WORK:

US 24
2L-RURAL
STA 1133+00
+
to
STA 1518+50
MCLEAN CO

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	1000 TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19,220.0
40600300	AGGREGATE (PRIME COAT)	TON	509.0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	5,231.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTTJOINT	SQ YD	2,671.0
40600990	TEMPORARY RAMP	SQ YD	433.0
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	10,495.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	499.0
40800030	AGGREGATE (PRIME COAT)	TON	12.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	524.0
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	117,807.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	6,775.0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	4,748.0
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	20.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	512.0
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	16.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,249.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	504.0
66700095	PERMANENT SURVEY MARKERS	EACH	2.0
66700505	PERMANENT SURVEY MARKERS, TYPE IV	EACH	2.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,490.0
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	86,739.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,166.0
* 72000100	SIGN PANEL - TYPE 1	SQ FT	18.0
* 72000200	SIGN PANEL - TYPE 2	SQ FT	32.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	86,739.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	480.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	480.0
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	875.0
X4421000	PARTIAL DEPTH PATCHING	TON	325.0
Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	4.0

* SPECIALTY ITEMS

FILE NAME :	USER NAME : stultsju	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\ppl\work\FW100T\STULTS\JW\d0117834\0570506-sh1-500.dgn		DRAWN -	REVISED -		317	(28)RS-4 & (29,30)RS-2	MCLEAN	54	4			
PLOT SCALE = 100.0000 "/ IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 70506				
PLOT DATE = 2/2/2009		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							