

SCHEDULE OF QUANTITIES

PERMANENT SURVEY MARKERS			
LOCATION	66700095	66700505	Z0070100
	PERMANENT SURVEY MARKER	PERMANENT SURVEY MARKER TYPE IV	SURVEY MONUMENT COVER ASSEMBLY
	EACH	EACH	EACH
1143+56	1		1
1156+76	1		1
1169+96		1	1
1175+24		1	1
TOTAL	2	2	4

PAVEMENT MARKING SCHEDULE									
LOCATION	LENGTH	PAINT PVM'T MK		TEMP PVM'T MK		SHORT TERM PAVT MK 70300100	WORK ZONE PAVT MK REM 70301000	RAISED REFLECTIVE PVM'T MK 78100100	RAISED REFL. PVM'T MK REM. 78300200
		4"	4"	4"	4"				
		WHITE	YELLOW	WHITE	YELLOW				
	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	SQ FT	SQ FT	SQ FT
MCLEAN COUNTY									
STA 1133+00 to STA 1134+00	100	200.0	25.0	200.0	25.0	27.3	3.0	1	1
STA 1134+00 to STA 1159+98	2,598	5196.0	649.5	5196.0	649.5	708.5	78.7	32	32
STA 1159+98 to STA 1169+06	908	1816.0	227.0	1816.0	227.0	247.6	27.5	11	11
STA 1169+06 to STA 1202+96	3,390	6780.0	847.5	6780.0	847.5	924.5	102.7	42	42
STA 1202+96 to STA 1493+56.58	29,061	58122.0	7265.3	58122.0	7265.3	7925.7	880.6	363	363
BRIDGE OMISSION 1493+56.58 TO 1494+43.42 (SN 057-0070)	86.84	173.7	21.7					1	1
STA 1494+43.42 to STA 1518+50	2,407	4814.0	601.8	4814.0	601.8	656.5	72.9	30	30
TOTAL	38,464	77,102	9,638	76,928	9,616	10,490	1,166	480	480