

| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|---------|---------------------------|--------------|-----------|
| 294 | * | MCLEAN | 22 | 5 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

*(14R2 & 15R1)RS-1

SUMMARY OF QUANTITIES

SHEET 2 OF 2

LOCATION OF WORK:

| | |
|-------------------|-------------------|
| FAS 294 | FAS 294 |
| OLD U.S. ROUTE 66 | OLD U.S. ROUTE 66 |
| RURAL | URBAN |
| STA. 2300+12 | STA. 2796+56 |
| TO | TO |
| STA. 2796+56 | STA. 2987+70 |

FUNDING BREAKOUT:

| | |
|----------|----------|
| 100% FED | 100% FED |
|----------|----------|

CONSTRUCTION TYPE CODE:

| | |
|------|------|
| 1000 | 1000 |
|------|------|

| CODE NO | ITEM | UNIT | TOTAL QUANTITY | QUANTITY | QUANTITY |
|------------|---|---------|----------------|-----------|----------|
| 44201803 | CLASS D PATCHES, TYPE II, 13 INCH | SQ YD | 3,037.0 | 2,194.0 | 843.0 |
| 44201807 | CLASS D PATCHES, TYPE III, 13 INCH | SQ YD | 283.0 | 204.0 | 79.0 |
| 44201809 | CLASS D PATCHES, TYPE IV, 13 INCH | SQ YD | 294.0 | 212.0 | 82.0 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 3,125.0 | 2,257.0 | 868.0 |
| 60622354 | CONCRETE MEDIAN, TYPE SM-6 (DOWELLED) | SQ FT | 140.0 | 140.0 | 0.0 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 4.0 | 3.0 | 1.0 |
| 67100100 | MOBILIZATION | L SUM | 1.0 | 0.7 | 0.3 |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1.0 | 0.7 | 0.3 |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1.0 | 0.7 | 0.3 |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1.0 | 0.7 | 0.3 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1.0 | 0.7 | 0.3 |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DAY | 2.0 | 2.0 | 0.0 |
| 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 13,627.0 | 9,841.0 | 3,786.0 |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 155,764.0 | 112,571.0 | 43,193.0 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 2,271.0 | 1,640.0 | 631.0 |
| • 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 129.0 | 129.0 | 0.0 |
| • 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 70.0 | 70.0 | 0.0 |
| • 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 138.0 | 90.0 | 48.0 |
| • 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 155,764.0 | 112,571.0 | 43,193.0 |
| • 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 852.0 | 615.0 | 237.0 |
| 89502380 | REMOVE EXISTING HANDHOLE | EACH | 2.0 | 2.0 | 0.0 |
| • | SPECIALTY ITEM | | | | |

PLOT DATE : 1/14/2009
 FILE NAME : c:\pwworking\pwworking\PROJECTS\70512\14R2\15R1\15R1RS-1.dgn
 PLOT SCALE : 42.3529 / IN.
 USER NAME : plr_sombr

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.S. ROUTE 294 (OLD U.S. ROUTE 66)
SECTION (14R2 & 15R1)RS-1
MCLEAN COUNTY

Sheet 2 of 2

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
DATE: 08/02/06 CHECKED BY: M.L.B.