

F.A.I. RT. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(74,10-4,1)RS-1	*	69	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* CHAMPAIGN & PIATT				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FAI - 74	
				PIATT COUNTY STA. 1258+09 TO STA. 1324+77.33 RURAL 100% FED	CHAMPAIGN COUNTY STA. 1324+09 TO 1501+00 RURAL 100% FED
20200100	EARTH EXCAVATION	CU YD	2.0	0.0	2.0
20400800	FURNISHED EXCAVATION	CU YD	57.0	0.0	57.0
21400100	GRADING AND SHAPING DITCHES	FOOT	100.0	0.0	100.0
* 25000210	SEEDING, CLASS 2A	ACRE	1.0	0.5	0.5
* 25000350	SEEDING, CLASS 7	ACRE	1.0	0.5	0.5
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	70.0	18.0	52.0
* 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	70.0	18.0	52.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	70.0	18.0	52.0
* 25100115	MULCH, METHOD 2	ACRE	1.0	0.5	0.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	78.0	20.0	58.0
28000300	TEMPORARY DITCH CHECKS	EACH	1.0	0.0	1.0
28000500	INLET AND PIPE PROTECTION	EACH	1.0	0.0	1.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	21,546.0	6,086.0	15,460.0
40600300	AGGREGATE (PRIME COAT)	TON	432.0	122.0	310.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	1.0	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	214.0	107.0	107.0
40600990	TEMPORARY RAMP	SQ YD	800.0	400.0	400.0
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	16,029.0	4,442.0	11,587.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	10,950.0	3,138.0	7,812.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	58.0	29.0	29.0

*SPECIALTY ITEM

SHEET 1 OF 3

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 F.A.I. ROUTE 74
 SECTION (74,10-4,1)RS-1
 CHAMPAIGN & PIATT COUNTY

SCALE: N/A
 DATE: 02-03-09

DRAWN BY: JMS
 CHECKED BY:

PLOT DATE = 2/6/2009
 FILE NAME = c:\pwworkspace\pwworkspace\PROJECTS\70527\shere\70527-shere.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = shere