CONTRACT NO. 70527

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(74,10-4,1)RS-1	*	69	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* CHAMPAIGN & PIATT

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FAI - 74 PIATT COUNTY STA. 1258+09 TO STA. 1324+77.33 RURAL 100% FED IOOO	FAI -74 CHAMPAIGN COUNTY STA. 1324+09 TO 1501+00 RURAL 100% FED IOOO
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,899.0	811.0	2,088.0
*	78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	96,623.0	27,030.0	69,593.0
*	78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 4"	FOOT	16,104.0	4,505.0	11,599.0
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,208.0	338.0	870.0
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	607.0	170.0	437.0
	X0322729	MATERIAL TRANSFER DEVICE	TON	26,979.0	7,580.0	19,399.0
	X0323583	SPEED INDICATOR SIGN	CAL DA	60.0	30.0	30.0
	X4401705	PARTIAL DEPTH REMOVAL	SQ YD	156.0	117.0	39.0
	X4421000	PARTIAL DEPTH PATCHING	TON	70.0	17.0	53.0
	X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	14.0	14.0
	Z0030150	IMPACT ATTENUATORS (NON-DIRECTIVE), TEST LEVEL 3 RE	EACH	6.0	0.0	6.0

* SPECIALTY ITEMS

SHEET 3 OF 3

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I. ROUTE 74

SECTION (74,10-4,1)RS-1

CHAMPAIGN & PIATT COUNTY

SCALE: N/A DRAWN BY: JMS

DATE: 02-03-09 CHECKED BY:

PLOT DATE = 2/5/2009
FILE NAME = c:\pw_work\PWIDOT\SHERERJM\dms88088\d570527-sht-soq.dgn
PLOT SCALE = 105.8824 ' / IN.
USER NAME = shererjm