

SCHEDULE OF QUANTITIES

SHEET 1 OF 5

40600982 HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT

STATION	TO	STATION	LENGTH (FT)	AVERAGE WIDTH (FT)	AREA (SQ YD)
IL 49 MAINLINE					
911+43.00		911+58.00	15.00	30.00	50.00
937+60.00		937+75.00	15.00	40.00	66.67
938+59.00		938+74.00	15.00	56.00	93.33
1012+65.00		1012+80.00	15.00	24.00	40.00
1017+62.00		1017+77.00	15.00	24.00	40.00
1133+50.00		1133+65.00	15.00	24.00	40.00
1133+93.00		1134+08.00	15.00	24.00	40.00
1214+97.00		1215+12.00	15.00	24.00	40.00
			TOTAL =	410.00	SQ YD
			USE =	410.00	SQ YD

* NOTE: SEE INCIDENTAL HOT-MIX ASPHALT SURFACING SCHEDULE FOR PRIVATE ENTRANCE QUANTITIES

44000155 HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"

STATION	TO	STATION	LENGTH (FT)	AVERAGE WIDTH (FT)	AREA (SQ YD)
911+58.00		911+79.60	21.60	30.00	72.00
911+79.60		933+37.00	2157.40	38.00	9,109.02
933+37.00		936+80.00	343.00	38.00	1,372.00
936+80.00		937+80.00	80.00	40.00	355.56
938+74.00		939+76.00	102.00	56.00	634.67
939+76.00		943+62.00	386.00	70.00	3,002.22
943+62.00		947+08.00	346.00	59.00	2,268.22
947+08.00		956+24.40	916.40	38.00	3,869.24
956+24.40		1012+65.00	5640.60	24.00	15,041.60
1017+77.00		1091+94.50 BK	7417.50	24.00	19,780.00
1092+00.00	AH	1133+50.00	4150.00	24.00	11,066.67
1134+08.00		1214+97.00	8089.00	24.00	21,570.67
			TOTAL =	88,141.87	SQ YD
			USE =	88,142.00	SQ YD

40600990 TEMPORARY RAMP

STATION		LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
911+43.00	RT	5.00	12.00	6.67
	LT	5.00	12.00	6.67
937+75.00	RT	5.00	18.00	10.00
	LT	5.00	18.00	10.00
938+59.00	RT	5.00	28.00	15.56
	LT	5.00	28.00	15.56
1012+80.00	RT	5.00	12.00	6.67
	LT	5.00	12.00	6.67
1017+77.00	RT	5.00	12.00	6.67
	LT	5.00	12.00	6.67
1133+65.00	RT	5.00	12.00	6.67
	LT	5.00	12.00	6.67
1133+93.00	RT	5.00	12.00	6.67
	LT	5.00	12.00	6.67
1215+12.00	RT	5.00	12.00	6.67
	LT	5.00	12.00	6.67
Madison	RT	5.00	24.00	13.33
Crittenden	RT	5.00	24.00	13.33
	LT	5.00	24.00	13.33
South	RT	5.00	24.00	13.33
	LT	5.00	24.00	13.33
Mary	RT	5.00	24.00	13.33
	LT	5.00	24.00	13.33
Coffeen	RT	5.00	24.00	13.33
	LT	5.00	24.00	13.33
Wabash	RT	5.00	24.00	13.33
	LT	5.00	24.00	13.33
First	RT	5.00	24.00	13.33
	LT	5.00	24.00	13.33
Second	RT	5.00	24.00	13.33
	LT	5.00	24.00	13.33
Third	RT	5.00	24.00	13.33
	LT	5.00	24.00	13.33
Fourth	RT	5.00	24.00	13.33
	LT	5.00	24.00	13.33
1200 N	Butt Joint	5.00	25.00	13.89
	EOP	2.50	25.00	6.94
1225 N	Butt Joint	5.00	20.00	11.11
	EOP	2.50	20.00	5.56
1250 N	Butt Joint	5.00	21.00	11.67
	EOP	2.50	21.00	5.83
Homer Lake Road	Butt Joint	5.00	19.00	10.56
	EOP	2.50	19.00	5.28
Homer Lake Road	Butt Joint	5.00	24.00	13.33
	EOP	2.50	24.00	6.67
Elvin St	Butt Joint	5.00	22.00	12.22
	EOP	2.50	22.00	6.11
Helton St	Butt Joint	5.00	25.00	13.89
	EOP	2.50	25.00	6.94

TOTAL = 514.44 SQ YD
USE = 514.00 SQ YD