FAP 325 | FAS 723

CONTRACT NO. 72795

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
723	*	MONTGOMERY	28	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 18(RS-4); 19(RS-7); 20Z(RS-5)
CONTRACT 72795

				FAP 325		FAS 723	
PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ESP 100 % FED 1000 PART "A"	ESP 100 % FED PARKING LANES 1000 PART "A"	ESP 100 % FED 1000 PART "B"	ESP 100 % FED PARKING LANES 1000 PART "A"
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	8.7	8.7			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28.0	19.5	1.7	4.8	2.0
40600300	AGGREGATE (PRIME COAT)	TON	74.0	51.2	4.5	12.8	5.5
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,374.2	956.1	94.4	209.2	114.5
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,582.0	2,968.2		1,613.8	
40600990	TEMPORARY RAMP	SQ YD	1,183.3	761.5		421.8	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,748.4	1,912.1	188.9	418.3	229.1
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	360.2	239.6		120.6	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4 INCH	SQ YD	32,426.0	22,648.5	2,248.4	4,802.0	2,727.1
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	260.0	150.0		110.0	
44004250	PAVED SHOULDER REMOVAL	SQ YD	50.0	50.0			
44200144	PAVEMENT PATCHING TY II, 12 INCH	SQ YD	180.0	150.0		30.0	
44200148	PAVEMENT PATCHING TY III, 12 INCH	SQ YD	50.0	50.0			
44200150	PAVEMENT PATCHING TY IV, 12 INCH	SQ YD	250.0	250.0			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	172.3	172.3			
48203029	HOT-MIX ASPHALT SHOULDERS 8"	SQ YD	323.3	323.3			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8.0	6.0		2.0	
67100100	MOBILIZATION	L SUM	1.0	1.0			
70100450	TRAFFIC CONTROL & PROTECTION STD 701201	L SUM	1.0	1.0			
70100460	TRAFFIC CONTROL & PROTECTION STD 701306	L SUM	1.0	0.5		0.5	
70100500	TRAFFIC CONTROL & PROTECTION STD 701326	L SUM	1.0	1.0			
70102620	TRAFFIC CONTROL & PROTECTION STD 701501	L SUM	1.0	0.5		0.5	
70102622	TRAFFIC CONTROL & PROTECTION STD 701502	L SUM	1.0	0.5		0.5	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	7.0	5.0		2.0	

	PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ESP 100 % FED 1000 PART "A"	ESP 100 % FED PARKING LANES 1000 PART "A"	ESP 100 % FED 1000 PART "B"	ESP 100 % FED PARKING LANES 1000 PART "A"
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,272.0	2,750.0		522.0	
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	342.0	219.0		123.0	
	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	19,840.0	18,900.0		940.0	
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	70.0	70.0			
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	194.0	48.0		146.0	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	363.5	305.5		58.0	
•	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	19,850.0	18,200.0		1,650.0	
•	78003100	PREFORMED PLASTIC PAVEMENT MARKING, TY B - LETTERS AND SYMBOLS	SQ FT	351.0	228.0		123.0	
•	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TY B - LINE 6"	FOOT	3,168.0	1,230.0	938.0	200.0	800.0
•	78003150	PREFORMED PLASTIC PAVEMENT MARKING, TY B - LINE 12"	FOOT	600.0	75.0	325.0		200.0
•	78003180	PREFORMED PLASTIC PAVEMENT MARKING, TY B - LINE 24"	FOOT	194.0	48.0		146.0	
•	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	166.0	166.0			
	78300200	RAISIED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	166.0	166.0			
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0			1.0	

• SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = Jan-26-2009 @1:33:47PM
FILE NAME = c:\projects\IPWIDOT\LAUDALINE\dms24266\72795-Shts-Sch..sht-800.dgn
PLOT SCALE = 1.000000 / IN.
USER NAME = laughlinr