

CONTRACT NO. 72795

| F.A.S. RTE.                     | SECTION | COUNTY                    | TOTAL SHEETS | SHEET NO. |
|---------------------------------|---------|---------------------------|--------------|-----------|
| 723                             | .       | MONTGOMERY                | 28           | 4         |
| STA.                            |         | TO STA.                   |              |           |
| FED. ROAD DIST. NO.             |         | ILLINOIS FED. AID PROJECT |              |           |
| • 18(RS-4); 19(RS-7); 202(RS-5) |         |                           |              |           |
| CONTRACT 72795                  |         |                           |              |           |

| HMA PAVING SCHEDULE PART "A" |    |             |               |              |                     |                        |                 |                 |                           |
|------------------------------|----|-------------|---------------|--------------|---------------------|------------------------|-----------------|-----------------|---------------------------|
| STATION BEGIN                |    | STATION END | DISTANCE (FT) | AREA (SQ YD) | LEVELING BINDER N70 | HMA SURFACE COURSE N70 | BIT. PRIME COAT | AGG/ PRIME COAT | HMA SURFACE REMOVAL 2.25" |
| 248+91                       | TO | 270+31      | 2,140.00      | 5889.6       | 247.4               | 494.7                  | 2.2             | 11.8            | 5,860.7                   |
| 270+31                       | TO | 295+57      | 2,526.00      | 11231.2      | 471.7               | 943.4                  | 4.3             | 22.5            | 11,231.2                  |
| 295+57                       | TO | 308+71      | 1,314.00      | 3602.2       | 151.3               | 302.6                  | 1.4             | 7.2             | 3,573.3                   |
| 309+83                       | TO | 325+57      | 1,574.00      | 4289.4       | 180.2               | 360.3                  | 1.6             | 8.6             | 4,231.7                   |
| TOTAL =                      |    |             |               | 25,012.4     | 1,050.5             | 2,101.0                | 9.5             | 50.0            | 24,896.9                  |

| AGGREGATE SHOULDER SCHEDULE |    |             |       |               |            |                          |
|-----------------------------|----|-------------|-------|---------------|------------|--------------------------|
| STATION BEGIN               |    | STATION END | LT/RT | DISTANCE (FT) | WIDTH (FT) | AGG SHOULDER TY B (TONS) |
| 248+91                      | TO | 270+84      | RT    | 2,193.00      | 3          | 41.5                     |
| 248+91                      | TO | 270+30      | LT    | 2,139.00      | 3          | 40.4                     |
| 289+67                      | TO | 292+75      | RT    | 308.00        | 3          | 5.8                      |
| 297+20                      | TO | 306+73      | RT    | 953.00        | 3          | 18.0                     |
| 298+70                      | TO | 306+73      | LT    | 803.00        | 3          | 15.2                     |
| 311+98                      | TO | 325+57      | RT    | 1,359.00      | 3          | 25.7                     |
| 311+98                      | TO | 325+57      | LT    | 1,359.00      | 3          | 25.7                     |
| TOTAL                       |    |             |       |               |            | 172.3                    |

| HMA SHOULDER SCHEDULE |    |             |       |               |            |                         |                             |
|-----------------------|----|-------------|-------|---------------|------------|-------------------------|-----------------------------|
| STATION BEGIN         |    | STATION END | LT/RT | DISTANCE (FT) | WIDTH (FT) | HMA SHOULDER 8" (SQ YD) | EXC. & GRADING SHLD (UNITS) |
| 270+84                | TO | 273+84      | RT    | 300.00        | 4          | 133.3                   | 3.0                         |
| 293+15.56             | TO | 295+72.11   | RT    | 256.55        | 3          | 85.5                    | 2.6                         |
| 295+57.23             | TO | 298+70.62   | LT    | 313.39        | 3          | 104.5                   | 3.1                         |
| TOTAL                 |    |             |       |               |            | 323.3                   | 8.7                         |

PLOT DATE = Jan-22-2009 02:14:03PM  
 FILE NAME = c:\pwworkspace\FMIDOT\LAIDLINR\cma24285\72795-Shd-Sch.dwg  
 PLOT SCALE = 1:10000  
 USER NAME = lajg@fup1

| REVISIONS |      | ILLINOIS DEPARTMENT OF TRANSPORTATION  |  |
|-----------|------|--|--|
| NAME      | DATE | <p>FAP ROUTE325<br/>         SCHEDULES<br/>         (PART "A")</p> <p>SCALE: VERT.<br/>         HORIZ.<br/>         DATE</p> <p>DRAWN BY<br/>         CHECKED BY</p> |  |
|           |      |  |  |
|           |      |  |  |
|           |      |  |  |
|           |      |  |  |
|           |      |  |  |