

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
723	*	MONTGOMERY	28	6

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* 18(RS-4); 19(RS-7); 20Z(RS-5)
CONTRACT 72795

HMA PAVING SCHEDULE PART "B"									
STATION BEGIN		STATION END	DISTANCE (FT)	AREA (SQ YD)	LEVELING BINDER N70	HMA SURFACE COURSE N70	BIT. PRIME COAT	AGG/ PRIME COAT	HMA SURFACE REMOVAL 2.25"
0+50	TO	16+80	1,630.00	7244.4	304.3	608.5	2.8	14.5	7,155.6
16+94	TO	17+98	104.00	462.2	19.4	38.8	0.2	0.9	373.4
TOTAL =				7,706.7	323.7	647.4	2.9	15.4	7,529.1

SIDEROAD SCHEDULE PART "B"											
LOCATION	TYPE OF ENTRANCE	MATERIAL TYPE	WIDTH	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT)	PR BIT. CONC. AVERAGE THICKNESS	HMA SURF. REM. - BUTT JOINT	TEMPORARY RQMPs	BIT (P. C.)	AGG (P. C.)	INCIDENTAL HMA SURF.	
(LT / RT) (STA) (+	(FE / PE / CE / MB) (RURAL / URBAN)	(EX / PR)	FOOT	FOOT	INCH	SQ. YD.	SQ. YD.	TON	TON	TON	
0+50 TO 0+80	SPRUCE ST	BIT	40	30	2.25	44.4	55.5				
RT STA. 0+99.92	S. R. MADISON ST	BIT	40	30	1.5	110.6	22.2	0.04	0.22	9.3	
LT STA. 4+38.12	S. R. HAMILTON ST.	BIT	40+	30+	1.5	402.5	22.2	0.15	0.81	33.8	
RT STA. 4+38.12	S. R. HAMILTON ST.	BIT	40+	30+	1.5	202.5	22.2	0.08	0.41	17.0	
LT STA. 8+24.33	S. R. WARREN ST.	BIT	40+	25	1.5	139.4	22.2	0.05	0.28	11.7	
RT STA. 8+24.34	S. R. WARREN ST.	BIT	40+	25	1.5	147.8	22.2	0.06	0.30	12.4	
LT STA. 12+06.32	S. R. FRANKLIN ST.	BIT	40+	23	1.5	115.9	22.2	0.04	0.23	9.7	
RT STA. 12+06.33	S. R. FRANKLIN ST.	BIT	40+	23	1.5	97.8	22.2	0.04	0.20	8.2	
LT STA. 16+05.61	S. R. FRONT ST.	BIT	40+	15	1.5	67.6	22.2	0.03	0.14	5.7	
RT STA. 16+05.62	S. R. FRONT ST.	BIT	40+	22	1.5	152.1	22.2	0.06	0.30	12.8	
16+49.8 TO 16+79.8	SPRUCE ST	BIT	40	30	2.25	44.4	55.5				
16+93.8 TO 17+23.8	SPRUCE ST	BIT	40	30	2.25	44.4	55.5				
17+68 TO 17+98	SPRUCE ST	BIT	40	30	2.25	44.4	55.5				
TOTAL =						1,613.8	421.8	0.5	2.9	120.6	

PLOT DATE = Jan-22-2009 08:43:44PM
 FILE NAME = c:\pawork\paw\72795\72795-Sht-Sch-wht-500.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = joughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAS ROUTE 723
SCHEDULES
(PART "B")

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
DATE