

ILLINOIS DEPARTMENT OF TRANSPORTATION						
SUMMARY OF QUANTITIES						
LOCATION OF WORK				CONSTRUCTION TYPE CODE		
SUMMARY OF QUANTITIES				ROADWAY		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ESP (100% FED) I000		
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	30	30		
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	1110	1110		
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	1225	1225		
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	375	375		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3985	3985		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	42,520	42,520		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,332	1,332		
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	112.5	112.5		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, (SPECIAL) TANGENT	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	326	326		
64200105	SHOULDER RUMBLE STRIP	FOOT	127,561	127,561		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	8	8		
67100100	MOBILIZATION	L SUM	1	1		

Rev

\* Specialty Item