

100% FED

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE		
					1000-2A ROADWAY RURAL	1000-2A ROADWAY URBAN	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)		UNIT	35	35		
20200100	EARTH EXCAVATION		CU YD	325	325		
20200500	EARTH EXCAVATION (WIDENING)	*	CU YD	58	58		
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	*	UNIT	7	7		
20400800	FURNISHED EXCAVATION		CU YD	555	555		
20800150	TRENCH BACKFILL		CU YD	87	87		
25000200	SEEDING, CLASS 2		ACRE	1.00	1.00		
25000400	NITROGEN FERTILIZER NUTRIENT		POUND	90	90		
25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	90	90		
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	90	90		
25100115	MULCH, METHOD 2		ACRE	1.00	1.00		
25100635	HEAVY DUTY EROSION CONTROL BLANKET		SQ YD	247	247		
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	300	300		
28000400	PERIMETER EROSION BARRIER		FOOT	625	625		
28000500	INLET AND PIPE PROTECTION		EACH	4	4		
28100707	STONE DUMPED RIPRAP, CLASS A4	*	SQ YD	1038	1038		
28200200	FILTER FABRIC		SQ YD	1038	1038		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"		SQ YD	142	142		
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"		SQ YD	261	261		
40200800	AGGREGATE SURFACE COURSE, TYPE B		TON	104	104		
40600200	BITUMINOUS MATERIALS (PRIME COAT)		TON	108.3	102.4	5.9	
40600300	AGGREGATE (PRIME COAT)		TON	570	539	31	
40600635	LEVELING BINDER (MACHINE METHOD), N70		TON	5644	5320	324	
40600895	CONSTRUCTING TEST STRIP		EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		SQ YD	160	160		
40600990	TEMPORARY RAMP	*	SQ YD	470	470		

FILE NAME = c:\p\work\PKWIDOT\LAUGHLINRL\dms23418\summary of quantities.dgn	USER NAME = laughlinr1	DESIGNED -	REVISED -
PLOT SCALE = 100.0002' / IN.		DRAWN -	REVISED -
PLOT DATE = Jan-23-2009 11:46:25AM		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: 1"=50' SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
745	103(RS-12), 104(RS-5)	ADAMS	109	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72877	