

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	CONSTRUCTION CODE 1000 ESP (100% FED) TOTAL QUANTITY
20400800	FURNISHED EXCAVATION	CU. YD.	100
35800100	PREPARATION OF BASE	SQ. YD.	2000
35800200	AGGREGATE BASE REPAIR	TON	36
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	55
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	87.3
40600300	AGGREGATE (PRIME COAT)	TON	446.5
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	8355
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	5393
40600990	TEMPORARY RAMP	SQ. YD.	309
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	16710
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	554
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ. YD.	21354
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ. YD.	183499
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ. YD.	4270
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ. YD.	1060
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ. YD.	100
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2492
48203100	HOT-MIX ASPHALT SHOULDERS	TON	818
60255500	MANHOLES TO BE ADJUSTED	EACH	9
60260100	INLETS TO BE ADJUSTED	EACH	7
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	17

* SPECIALTY ITEMS

FILE NAME =	USER NAME = leughlinr1	DESIGNED - MJS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS ROUTE 9 DALLAS CITY TO LA HARPE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEABBREV#		DRAWN -	REVISED -			685	D-6 Resurfacing 2011-1	Hancock	44	3	
	PLOT SCALE = 2,0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 72983					
	PLOT DATE = Feb-23-2009 10:22:22 AM	DATE - FEB 2008	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT		