

THERMOPLASTIC PAVEMENT MARKING - LINE 5"						
LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	NUMBER OF LINES	LENGTH (FT)	
JEFFERSON						
YELLOW						
STA. 150+00.00 TO STA. 163+19.80	SKIP - DASH (CENTER)	1319.8	10' @ 40'	2	659.90	
STA. 169+81.80 TO STA. 191+93.58	SKIP - DASH (CENTER)	2211.8	10' @ 40'	2	1105.89	
STA. 150+00.00 TO STA. 163+19.80	SOLID (CENTER)	1319.8	-	2	2639.60	
STA. 163+19.80 TO STA. 163+65.00	SOLID (CENTER)	45.2	-	4	180.80	
STA. 163+65.00 TO STA. 165+67.00	SOLID (CENTER)	202.0	-	2	404.00	
STA. 167+04.00 TO STA. 169+33.00	SOLID (CENTER)	229.0	-	2	458.00	
STA. 169+33.00 TO STA. 169+81.80	SOLID (CENTER)	48.8	-	4	195.20	
STA. 169+81.80 TO STA. 191+93.58	SOLID (CENTER)	2211.8	-	2	4423.56	
BRUNS LANE						
STA. 55+20.57 TO STA. 56+76.00	SOLID (CENTER)	155.4	-	2	310.86	
STA. 58+16.0 TO STA. 59+32.7	SOLID (CENTER)	116.7	-	2	233.36	
				TOTAL	10611.2	

THERMOPLASTIC PAVEMENT MARKING - LINE 8"		
LOCATION STATION	DESCRIPTION	LENGTH (FT)
JEFFERSON		
WHITE		
STA. 165+69.00	LEFT ISLAND	158.0
STA. 167+00.00	RIGHT ISLAND	141.0
STA. 221+75.00	LEFT ISLAND	75.0
STA. 222+90.00	LEFT ISLAND	85.0
TOTAL		459.0

THERMOPLASTIC PAVEMENT MARKING - LINE 12"		
LOCATION STATION	DESCRIPTION	LENGTH (FT)
JEFFERSON		
WHITE		
STA. 165+69.00	LEFT ISLAND	84.0
STA. 167+00.00	RIGHT ISLAND	59.0
STA. 221+75.00	LEFT ISLAND	25.0
STA. 222+90.00	LEFT ISLAND	25.0
STA. 236+25.00	LEFT ISLAND	62.0
TOTAL		255.0

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS & SYMBOLS"					
LOCATION STATION TO STATION	DESCRIPTION	ARROW TYPE	NUMBER OF ARROWS	AREA (SQ FT)	TOTAL AREA (SQ FT)
JEFFERSON					
WHITE					
STA. 150+00.00 TO STA. 163+19.80	CENTER	TURN ARROW	12	15.6	187.20
STA. 163+75.00 TO STA. 165+67.00	LEFT TURN LANE	TURN ARROW	3	15.6	46.80
STA. 163+50.00 TO STA. 165+69.00	RIGHT TURN LANE	TURN ARROW	3	15.6	46.80
STA. 169+81.80 TO STA. 191+93.58	CENTER	TURN ARROW	22	15.6	343.20
STA. 166+97.50 TO STA. 168+75.00	RIGHT TURN LANE	TURN ARROW	3	15.6	46.80
STA. 167+04.00 TO STA. 169+29.00	LEFT TURN LANE	TURN ARROW	3	15.6	46.80
STA. 195+25.56 TO STA. 196+55.00	CENTER	THROUGH ARROW	2	11.5	23.00
STA. 195+25.65 TO STA. 196+55.00	RIGHT TURN LANE	COMBINATION	2	26	52.00
STA. 195+25.25 TO STA. 198+70.00	LEFT TURN LANE	TURN ARROW	4	15.6	62.40
STA. 209+34.00 TO STA. 210+00.00	RIGHT TURN LANE	COMBINATION	1	26	26.00
STA. 209+34.00 TO STA. 210+00.00	CENTER	THROUGH ARROW	1	11.5	11.50
STA. 209+34.00 TO STA. 210+00.00	LEFT TURN LANE	COMBINATION	1	26	26.00
STA. 223+00.00 TO STA. 225+02.00	RIGHT TURN LANE	TURN ARROW	3	15.6	46.80
STA. 223+00.00 TO STA. 225+03.00	LEFT TURN LANE	TURN ARROW	3	15.6	46.80
STA. 234+11.00 TO STA. 235+08.00	RIGHT TURN LANE	TURN ARROW	2	15.6	31.20
STA. 237+31.00 TO STA. 238+72.00	RIGHT TURN LANE	TURN ARROW	3	15.6	46.80
STA. 237+31.00 TO STA. 238+11.00	LEFT TURN LANE	TURN ARROW	3	15.6	46.80
STA. 247+75.00 TO STA. 250+79.00	LEFT TURN LANE	COMBINATION	4	26	104.00
STA. 258+43.00	RIGHT	HANDICAPPED SYMBOL	1	4.6	4.60
BRUNS LANE					
WHITE					
STA. 55+20.57 TO STA. 56+76.00	LEFT TURN LANE	TURN ARROW	2	15.6	31.20
STA. 58+16.0 TO STA. 59+32.7	LEFT TURN LANE	TURN ARROW	2	15.6	31.20
STA. 55+20.57 TO STA. 56+47.00	RIGHT TURN LANE	TURN ARROW	2	15.6	31.20
STA. 58+16.00 TO STA. 59+32.68	RIGHT TURN LANE	TURN ARROW	1	15.6	15.60
				TOTAL	1354.7

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"		
LOCATION STATION	DESCRIPTION	LENGTH (FT)
JEFFERSON		
WHITE		
STA. 165+69.00	MAINLINE	24.0
STA. 165+67.00	RIGHT TURN LANE	12.0
STA. 165+69.00	LEFT TURN LANE	12.0
STA. 166+97.50	MAINLINE	24.0
STA. 166+97.50	RIGHT TURN LANE	12.0
STA. 167+04.00	LEFT TURN LANE	12.0
STA. 195+26.00	MAINLINE/LEFT TURN LANE	36.0
STA. 223+00.00	MAINLINE/LEFT TURN LANE	50.0
STA. 237+20.00	MAINLINE/LEFT & RIGHT TURN	69.0
STA. 247+80.00	MAINLINE/LEFT TURN LANE	56.0
BRUNS LANE		
STA. 56+76.00	MAINLINE	36.0
STA. 58+16.00	MAINLINE	36.0
STA. 56+49.00	RIGHT TURN LANE	16.0
STA. 58+38.0	RIGHT TURN LANE	16.0
TOTAL		411.0