

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE			
				100% FED.		100% STATE	
				1000	RURAL	1000	RURAL
M2800800	MULCH, METHOD 2	HA	2.9	2.9			
M2810707	STONE DUMPED RIPRAP, CLASS A4	SQ M	1,156	1,010	146		
M2820200	FILTER FABRIC	SQ M	1,703	1,557	146		
M2830400	AGGREGATE DITCH	M TON	293	293			
M3111100	SUB-BASE GRANULAR MATERIAL, TYPE B 100MM	SQ M	7,303	410	6,893		
M3511010	AGGREGATE BASE COURSE, TYPE B	M TON	253	167	86		
M3530200	PORTLAND CEMENT CONCRETE BASE COURSE, 200MM	SQ M	2,760		2,760		
M3550500	HOT-MIX ASPHALT BASE COURSE, 200MM	SQ M	353	353			
M4021010	AGGREGATE SURFACE COURSE, TYPE B	M TON	336	293	43		
M4021200	AGGREGATE FOR TEMPORARY ACCESS	M TON	680	96	584		
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	22,486	11,953	10,533		
M4060300	AGGREGATE (PRIME COAT)	M TON	100	55	45		
M4060895	CONSTRUCTING TEST STRIP	EACH	3	2	1		
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	297	297			
M4060990	TEMPORARY RAMP	SQ M	34	34			
M4062135	LEVELING BINDER (MACHINE METHOD), N70	M TON	2,901	1,505	1,396		
M4063340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	3,120	1,747	1,373		
M4080100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	3,326	1,345	1,981		
M4080300	AGGREGATE (PRIME COAT)	M TON	1	1			
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	285	126	159		
M4200200	PORTLAND CEMENT CONCRETE PAVEMENT 200MM	SQ M	2,252		2,252		

* SEE SPECIAL PROVISIONS

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES SCALE _____ DRAWN BY KOJ DATE FEBRUARY 6, 2009 CHECKED BY LWJ

PLOT DATE = 2/17/2009
 FILE NAME = H:\4420\Contract\74349\SHT_004.dwg