

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|---------|----------|------------------|-----------|
| 781 | 2ZRS-1 | CRAWFORD | 191 | 18 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

TREE REMOVAL

| LOCATION | | | EXISTING OCTOBER, 1996 TREE SURVEY | COMMON NAME | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | TREE REMOVAL (OVER 15 UNITS DIAMETER) | TREE REMOVAL HECTARES |
|---|--------|-------|------------------------------------|---------------|---------------------------------------|---------------------------------------|-----------------------|
| STATION | OFFSET | RT/LT | MM | | UNIT | UNIT | HA |
| RURAL | | | | | | | |
| 1+772.4 | 10.7 | LT | | | 6 | | |
| 1+787.4 | 10.9 | LT | | | 6 | | |
| 1+886.5 | 7.8 | RT | | | 6 | | |
| 1+886.5 | 18.4 | RT | | | 6 | | |
| 1+887.3 | 15.1 | RT | 275 | CMN PERSIMMON | 11 | | |
| 1+888.3 | 18.1 | RT | | | 6 | | |
| 1+889.9 | 17.5 | RT | | | 6 | | |
| 1+923.7 | 10.5 | RT | | | 6 | | |
| 1+959.2 | 29.1 | RT | | | 6 | | |
| 1+966.7 | 8.9 | LT | 1025 | RED MAPLE | | 40 | |
| 1+970.2 | 24.7 | RT | 450 | RED MAPLE | | 18 | |
| 2+009.3 | 9.8 | LT | | | 6 | | |
| 2+036.0 TO 2+120.0 | 13.0 | RT | | | | | 0.04 |
| 2+327.8 | 20.0 | RT | | | 6 | | |
| 2+440.0 | 19.8 | RT | | | 6 | | |
| 2+555.6 | 8.2 | LT | 325 | RED MAPLE | 13 | | |
| 2+564.5 | 8.1 | LT | 450 | RED MAPLE | | 18 | |
| 2+582.3 | 9.3 | LT | 375 | RED MAPLE | 15 | | |
| 2+590.7 | 9.5 | LT | 500 | SUGAR MAPLE | | 20 | |
| 2+598.2 | 8.6 | LT | 600 | RED MAPLE | | 24 | |
| | | | | | 105 | 120 | 0.04 |
| OBLONG | | | | | | | |
| 2+906.2 | 5.8 | LT | 800 | RED MAPLE | | 28 | |
| 2+924.4 | 6.0 | LT | 925 | RED MAPLE | | 37 | |
| 2+943.4 | 6.5 | LT | 800 | RED MAPLE | | 28 | |
| 2+959.6 | 5.9 | LT | 1075 | RED MAPLE | | 43 | |
| 2+971.6 | 11.2 | LT | | | 6 | | |
| 2+987.1 | 10.6 | LT | | | 6 | | |
| 2+997.9 | 10.2 | LT | | | 6 | | |
| 3+027.9 | 5.7 | LT | 375 | RED MAPLE | 15 | | |
| 3+036.8 | 5.9 | LT | 550 | RED MAPLE | | 22 | |
| 3+044.7 | 6.5 | LT | 550 | RED MAPLE | | 22 | |
| 3+058.0 | 6.1 | LT | 350 | RED MAPLE | 14 | | |
| 3+069.6 | 5.6 | LT | 625 | RED MAPLE | | 25 | |
| 3+099.3 | 6.3 | LT | 725 | RED MAPLE | | 29 | |
| 3+108.1 | 6.1 | LT | 500 | RED MAPLE | | 20 | |
| 3+115.7 | 6.1 | LT | 425 | RED MAPLE | 17 | | |
| 3+129.2 | 9.6 | LT | 525 | SUGAR MAPLE | | 21 | |
| 3+135.2 | 9.9 | LT | | | 6 | | |
| 3+142.3 | 9.7 | LT | | | 6 | | |
| 3+217.2 | 9.8 | LT | 450 | SUGAR MAPLE | | 18 | |
| 3+281.7 | 9.4 | RT | | | 6 | | |
| 3+291.3 | 11.2 | RT | | | 6 | | |
| 3+765.0 | 6.6 | LT | 325 | RED MAPLE | 13 | | |
| 3+844.0 | 9.6 | LT | | | 6 | | |
| 3+862.0 | 9.7 | LT | | | 6 | | |
| 4+224.4 | 6.8 | LT | | | 6 | | |
| 4+231.2 | 6.9 | LT | | | 6 | | |
| 4+259.9 | 6.5 | LT | | WILLOW | 6 | | |
| 4+268.8 | 6.7 | LT | | WILLOW | 6 | | |
| 4+468.2 | 11.7 | LT | | | 6 | | |
| | | | | | 143 | 293 | 0.00 |
| TOTALS | | | | | 248 | 413 | 0.04 |
| TOTALS ROUNDED FOR SUMMARY SHEET | | | | | 248 | 413 | 0.1 |

GUARDRAIL REMOVAL

| LOCATION | | | | GUARDRAIL REMOVAL |
|--|-------|-------|--|-------------------|
| | | | | M6320030 |
| | RT/LT | METER | | |
| OBLONG | | | | |
| 2+762.000 TO 2+768.000 | RT | 6.6 | | |
| TOTAL | | | | 6.6 |
| TOTAL ROUNDED FOR SUMMARY SHEET | | | | 7 |

PLOT DATE = 2/6/2009
 FILE NAME = H:\4420\Contract 74349\SH_014_sch.dwg

H. M. & G. NO. 4420

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|--|
| NAME | DATE | |
| | | SCHEDULE OF QUANTITIES SCALE NO SCALE DRAWN BY KOJ DATE FEBRUARY 6, 2009 CHECKED BY LWJ |
| | | |
| | | |
| | | |
| | | |
| | | |