

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	20
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

HOT-MIX ASPHALT SURFACE REMOVAL

LOCATION				HOT-MIX ASPHALT SURFACE REMOVAL							TEMPORARY RAMP
				VARIABLE DEPTH			BUTT JOINT	M4060982	M4060990		
				15mm @ CENTERLINE	25mm @ CENTERLINE	40mm @ CENTERLINE					
STATION	TO	STATION	RT/LT	M4400715 SQ M	M4400725 SQ M	M4400740 SQ M	M4400950 SQ M	M4400950 SQ M	M4060982 SQ M	M4060990 SQ M	
RURAL											
0+915.000	TO	0+935.000	LT & RT						151.7	15.2	
0+935.000	TO	2+756.900	LT & RT	13,570.7							
				13,570.7	0.0	0.0	0.0	0.0	151.7	15.2	
OBLONG											
2+756.900	TO	3+155.000	LT	1,353.5							
2+756.900	TO	2+770.950	RT	54.6							
2+770.950	TO	3+155.000	RT	1,305.8							
3+155.000	TO	3+350.000	LT & RT		1,326.0						
3+350.000	TO	3+394.700	LT & RT	304.0							
3+394.700	TO	3+495.000	LT & RT	872.6							
3+495.000	TO	3+535.000	LT			212.0					
3+495.000	TO	3+535.000	RT	136.0							
3+535.000	TO	3+555.000	LT & RT				174.0				
3+555.000	TO	3+625.000	LT & RT					608.9			
3+625.000	TO	3+736.200	LT & RT					967.5			
3+736.200	TO	3+755.000	LT & RT					127.8			
3+755.000	TO	4+055.000	LT & RT	2,040.0							
4+055.000	TO	4+360.000	LT & RT		2,074.0						
4+360.000	TO	4+440.000	LT & RT	513.6							
4+440.000	TO	4+475.071	LT				132.4				
4+440.000	TO	4+475.071	RT	103.7							
				6,683.8	3,400.0	212.0	306.4	1,095.3	608.9	0.0	
RURAL											
4+475.071	TO	4+635.000	LT				594.7				
4+475.071	TO	4+635.000	RT	483.6							
4+633.500	TO	4+653.500	LT & RT						144.7		
4+653.500	TO	4+874.474	LT & RT			1,988.8				18.0	
				483.6	0.0	1,988.8	594.7	0.0	0.0	144.7	
										18.0	
TOTALS				20,738.1	3,400.0	2,200.8	901.1	1,095.3	608.9	296.4	33.2
TOTALS ROUNDED FOR SUMMARY SHEET				20,739	3,400	2,201		2,606		297	34

COMBINATION CURB AND GUTTER REMOVAL

LOCATION				COMBINATION CURB AND GUTTER REMOVAL
				M4402040
STATION	TO	STATION	LT/RT	METER
OBLONG				
STA 2+756.9	TO	JEFFERSON STREET	RT	281.50
TR 150	TO	JOY STREET	LT	89.40
JOY STREET	TO	MADISON STREET	LT	63.00
MADISON STREET	TO	JEFFERSON STREET	LT	84.90
JEFFERSON STREET	TO	WASHINGTON STREET	LT	112.60
JEFFERSON STREET	TO	WASHINGTON STREET	RT	59.50
WASHINGTON STREET	TO	JACKSON STREET	LT	68.20
WASHINGTON STREET	TO	JACKSON STREET	RT	65.20
JACKSON STREET	TO	WILSON STREET	LT	77.60
JACKSON STREET	TO	ADAMS STREET	RT	89.70
WILSON STREET	TO	RANGE STREET	LT	156.50
ADAMS STREET	TO	RANGE STREET	RT	68.40
RANGE STREET	TO	GARFIELD STREET	LT	82.20
RANGE STREET	TO	GARFIELD STREET	RT	84.80
GARFIELD STREET	TO	GRANT STREET	LT	81.40
GARFIELD STREET	TO	GRANT STREET	RT	10.60
GRANT STREET	TO	HARRISON STREET	LT	84.90
HARRISON STREET	TO	TAYLOR STREET	LT	85.20
GRANT STREET	TO	TAYLOR STREET	RT	137.20
TAYLOR STREET	TO	STA 4+475.071	LT	332.20
TAYLOR STREET	TO	ROOSEVELT STREET	RT	199.20
ROOSEVELT STREET	TO	STA 4+475.071	RT	181.20
TOTALS				2,495.40
TOTALS ROUNDED FOR SUMMARY SHEET				2,496

REMOVAL OF EXISTING STRUCTURES

LOCATION	DESCRIPTION	REMOVAL OF EXISTING STRUCTURES
STATION	RT/LT	50100X00 EACH
OBLONG		
STA 3+482	RT	CONCRETE BOLLARD; APPROX. 1.5m(L) X 1.2m(W) X 0.3m(H)
STA 3+486	RT	CONCRETE BOLLARD; APPROX. 1.4m(L) X 1.3m(W) X 0.3m(H)
STA 3+858	LT	CONCRETE WALL; APPROX. 37.5m(L) X 0.2m(W) X 0.5m(H)
STA 3+852	LT	BRICK COLUMN; APPROX. 500mm(L) X 500mm(W) X 900mm(H)
STA 3+854	LT	BRICK COLUMN; APPROX. 500mm(L) X 500mm(W) X 900mm(H)
STA 4+289	RT	BRICK COLUMN; APPROX. 450mm(L) X 450mm(W) X 900mm(H)
STA 4+295	RT	BRICK COLUMN; APPROX. 450mm(L) X 450mm(W) X 900mm(H)

STORM SEWER REMOVAL

LOCATION			STORM SEWER REMOVAL					TRENCH BACKFILL	
			150	300	450	525	600		
STATION	LT/RT/AR		M5510010 METER	M5510025 METER	M5510045 METER	M5510055 METER	M5510060 METER	M2080150 CU. M	
STA 2+767.500	TO	3+131.700	RT				364.2	196.7	
STA 3+131.700	TO	3+218.100	RT			86.4		32.4	
STA 3+206.600			RT	9.0				1.6	
STA 3+216.600			RT	9.0				1.6	
STA 3+391.000	TO	3+563.700	RT		172.7			62.2	
STA 3+563.700	TO	3+567.300	RT		7.0				
STA 3+652.500	TO	3+656.800	RT		4.3			0.7	
STA 3+656.900			AR	25.3				9.1	
STA 3+652.500	TO	3+656.800	LT		4.3			0.7	
STA 4+403.700			AR		13.4				
STA 4+448.200	TO	4+457.200	LT		9.0			1.6	
TOTALS				18.0	42.9	193.1	86.4	364.2	306.6
TOTALS ROUNDED FOR SUMMARY SHEET				18	43	194	87	365	307

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p>SCALE NO SCALE DRAWN BY KOJ</p> <p>DATE FEBRUARY 6, 2009 CHECKED BY LWJ</p>

PLOT DATE = 2/6/2009
FILE NAME = H:\4428\Contract 74349\BHT_014_sch_all_schedules_V8.dgn

H. M. & G. NO. 4420