

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|---------|----------|------------------|-----------|
| 781 | 2ZRS-1 | CRAWFORD | 191 | 21 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

PIPE CULVERT REMOVAL/REMOVE EXISTING CULVERTS

| LOCATION | | EXISTING MATERIAL | SIZE (mm) | EXISTING END TREATMENT | | REMOVE EXISTING CULVERTS | PIPE CULVERT REMOVAL |
|---|-------|-------------------|-----------|--------------------------------|------------|--------------------------|----------------------|
| STATION | LT/RT | | | UPSTREAM | DOWNSTREAM | M5010521 METER | M5010522 METER |
| RURAL | | | | | | | |
| 0+950.000 | RT | CMP | 420 | | | | 7.0 |
| 1+201.500 | LT | CMP | 460 | | | | 10.0 |
| 1+427.000 | RT | CMP | 762X482 | | | | 9.0 |
| 1+518.000 | | CONC BOX | 1280X790 | CONC HDWL | CONC HDWL | 12.9 | |
| 1+595.000 | RT | CMP | 450 | | | | 9.0 |
| 1+882.500 | | CONC BOX | 1800X1260 | CONC HDWL | CONC HDWL | 11.9 | |
| 1+952.000 | LT | CMP | 300 | | | | 5.0 |
| 2+196.000 | LT | VCP | 380 | | | | 5.5 |
| 2+403.000 | RT | CMP | 1470 | CONC HDWL'S / INCL. SLOPEWALLS | | | 15.5 |
| 2+535.000 | LT | CMP | 380 | | | | 8.0 |
| | | | | | | 24.8 | 69.0 |
| OBLONG | | | | | | | |
| 2+759.000 | RT | CMP | 1420 | | | | 12.6 |
| 2+767.500 | LT | CONC BOX | 460X610 | CONC HDWL | CONC HDWL | 9.2 | |
| 3+915.200 | AR | CONC BOX | 900X900 | | | 13.1 | |
| 3+938.200 | LT | CONC BOX | 900X900 | | CONC HDWL | 49.0 | |
| 4+441.500 | RT | CMP | 450 | | | | 9.2 |
| 4+461.000 | LT | CMP | 375 | | | | 8.2 |
| 4+483.000 | LT | CMP | 375 | | | | 28.0 |
| | | | | | | 71.3 | 58.0 |
| RURAL | | | | | | | |
| 4+529.000 | RT | CMP | 450 | | | | 9.8 |
| 4+583.000 | LT | CMP | 450 | CONC HDWL | CONC HDWL | | 9.0 |
| 4+601.300 | RT | CMP | 450 | | | | 9.2 |
| 4+618.800 | LT | CMP | 450 | CONC HDWL | | | 15.3 |
| | | | | | | 0 | 43.3 |
| TOTALS | | | | | | 96.1 | 170.30 |
| TOTALS ROUNDED FOR SUMMARY SHEET | | | | | | 97 | 171 |

REMOVING MANHOLES/INLETS

| LOCATION | | | REMOVING MANHOLES | REMOVING INLETS |
|---------------|--------|-------|-------------------|-----------------|
| STATION | DIST | RT/LT | 60500040 EACH | 60500060 EACH |
| OBLONG | | | | |
| STA 2+769.7 | 5.6 m | RT | 1 | |
| STA 2+770.9 | 5.0 m | RT | | 1 |
| STA 2+777.3 | 4.5 m | LT | | 1 |
| STA 2+985.1 | 4.5 m | LT | | 1 |
| STA 2+985.1 | 4.5 m | RT | | 1 |
| STA 3+130.3 | 4.5 m | LT | | 1 |
| STA 3+131.8 | 4.5 m | RT | | 1 |
| STA 3+206.3 | 5.9 m | RT | | 1 |
| STA 3+216.6 | 10.9 m | LT | | 1 |
| STA 3+218.1 | 4.5 m | RT | | 1 |
| STA 3+218.2 | 4.5 m | LT | | 1 |
| STA 3+305.3 | 4.5 m | LT | | 1 |
| STA 3+305.6 | 4.5 m | RT | | 1 |
| STA 3+391.1 | 7.1 m | LT | | 1 |
| STA 3+391.0 | 6.6 m | RT | | 1 |
| STA 3+480.3 | 6.6 m | RT | 1 | |
| STA 3+563.8 | 6.9 m | RT | 1 | |
| STA 3+566.9 | 9.4 m | RT | | 1 |
| STA 3+652.2 | 6.6 m | LT | | 1 |
| STA 3+657.0 | 6.9 m | LT | 1 | |
| STA 3+652.3 | 6.4 m | RT | | 1 |
| STA 3+656.8 | 7.4 m | RT | 1 | |
| STA 3+740.2 | 6.3 m | LT | | 1 |
| STA 3+824.0 | 4.5 m | LT | | 1 |
| STA 3+915.1 | 9.8 m | RT | | 1 |
| STA 3+915.1 | 5.7 m | RT | | 1 |
| STA 3+931.6 | 4.5 m | LT | | 1 |
| STA 3+931.6 | 4.5 m | RT | | 1 |
| STA 4+379.5 | 4.5 m | LT | | 1 |
| STA 4+403.6 | 7.9 m | LT | | 1 |
| STA 4+448.1 | 10.8 m | LT | | 1 |
| STA 4+457.3 | 11.0 m | LT | | 1 |
| TOTAL | | | 5 | 28 |

PAVEMENT REMOVAL

| LOCATION | | | | PAVEMENT REMOVAL |
|---|----|-----------|-------|------------------|
| STATION | TO | STATION | LT/RT | M4402000 SQ M |
| RURAL | | | | |
| 1+955.000 | | | RT | 62.97 |
| 2+050.000 | | | RT | 212.94 |
| | | | | 275.91 |
| OBLONG | | | | |
| 2+756.900 | TO | 3+394.700 | LT | 1,038.88 |
| 2+770.950 | TO | 3+394.700 | RT | 1,003.69 |
| 3+394.700 | TO | 3+736.200 | LT | 681.03 |
| 3+394.700 | TO | 3+736.200 | RT | 1,361.94 |
| 3+736.200 | TO | 4+475.071 | LT | 1,109.88 |
| 3+736.200 | TO | 4+475.071 | RT | 1,001.21 |
| | | | | 6,196.63 |
| TOTAL | | | | 6,472.54 |
| TOTALS ROUNDED FOR SUMMARY SHEET | | | | 6,473 |

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|--|
| NAME | DATE | |
| | | <p align="center">SCHEDULE OF QUANTITIES</p> <p>SCALE NO SCALE DRAWN BY KOJ</p> <p>DATE FEBRUARY 6, 2009 CHECKED BY LWJ</p> |
| | | |
| | | |
| | | |
| | | |
| | | |

PLOT DATE = 2/6/2009
 FILE NAME = H:\4420\Contract 74349\SH_014_sch.dwg

H. M. & G. NO. 4420