

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SEEDING/SODDING/MULCH

LOCATION				SEEDING CLASS 2	SODDING	SUPPLEMENTAL WATERING			FERTILIZER NUTRIENTS			MULCH METHOD 2	GRADING AND SHAPING SPECIAL
						QTY PER WATERING	NUMBER OF WATERINGS	SUPPLEMENTAL WATERING	NITROGEN	POTASSIUM	PHOSPHORUS		
STATION	LT/RT	HA	SQ M	L	EACH	UNIT	KG	KG	KG	HA	SQ M		
RURAL													
STA 0+915	TO	STA 2+756.9	LT	1.18			117.62	117.62	117.62	1.18			
STA 0+915	TO	STA 2+756.9	RT	1.80			179.52	179.52	179.52	1.46			
				2.97	0		297.14	297.14	297.14	2.63	0		
OBLONG													
STA 2+756.9	TO	TR 150	LT	0.01			0.82	0.82	0.82	0.01			
TR 150	TO	JOY STREET	LT		371	5,565	27.8	2.60	2.60	2.60		371	
STA 2+756.9	TO	JEFFERSON STREET	RT		1,257	18,854	5	94.3	8.80	8.80		1,257	
JOY STREET	TO	MADISON STREET	LT		287	4,298	5	21.5	2.01	2.01		287	
MADISON STREET	TO	JEFFERSON STREET	LT		670	10,049	5	50.2	4.69	4.69		670	
JEFFERSON STREET	TO	WASHINGTON STREET	LT		252	3,774	5	18.9	1.76	1.76		252	
JEFFERSON STREET	TO	WASHINGTON STREET	RT		236	3,542	5	17.7	1.65	1.65		236	
WASHINGTON STREET	TO	JACKSON STREET	LT		234	3,508	5	17.5	1.64	1.64		234	
WASHINGTON STREET	TO	JACKSON STREET	RT		270	4,056	5	20.3	1.89	1.89		270	
JACKSON STREET	TO	WILSON STREET	LT		274	4,116	5	20.6	1.92	1.92		274	
JACKSON STREET	TO	ADAMS STREET	RT		252	3,779	5	18.9	1.76	1.76		252	
WILSON STREET	TO	STA 3+483	LT		137	2,059	5	10.3	0.96	0.96		137	
STA 3+483	TO	RANGE STREET	LT		13	194	5	1.0	0.09	0.09		13	
ADAMS STREET	TO	RANGE STREET	RT		16	241	5	1.2	0.11	0.11		16	
RANGE STREET	TO	GARFIELD STREET	LT		8	124	5	0.6	0.06	0.06		8	
GARFIELD STREET	TO	GRANT STREET	LT		136	2,045	5	10.2	0.95	0.95		136	
GARFIELD STREET	TO	GRANT STREET	RT		62	932	5	4.7	0.43	0.43		62	
GRANT STREET	TO	HARRISON STREET	LT		287	4,310	5	21.6	2.01	2.01		287	
HARRISON STREET	TO	TAYLOR STREET	LT		314	4,704	5	23.5	2.20	2.20		314	
GRANT STREET	TO	TAYLOR STREET	RT		557	8,354	5	41.8	3.90	3.90		557	
TAYLOR STREET	TO	HAYES STREET	LT		687	10,302	5	51.5	4.81	4.81		687	
TAYLOR STREET	TO	ROOSEVELT STREET	RT		798	11,968	5	59.8	5.59	5.59		798	
HAYES STREET	TO	LEGION PARKWAY	LT		541	8,114	5	40.6	3.79	3.79		541	
ROOSEVELT STREET	TO	STA 4+475	RT		1,426	21,387	5	106.9	9.98	9.98		1,426	
LEGION PARKWAY	TO	STA 4+475	LT		730	10,949	5	54.7	5.11	5.11		730	
				0.01	9,815		736.1	69.53	69.53	69.53	0.01	9,815	
RURAL													
STA 4+475.071	TO	STA 4+874.474	LT	0.08			8.27	8.27	8.27	0.08			
STA 4+475.071	TO	STA 4+874.474	RT	0.10			9.94	9.94	9.94	0.10			
				0.18	0		18.21	18.21	18.21	0.18	0		
TOTALS				3.16	9,815		736.1	384.88	384.88	384.88	2.83	9,815	
TOTALS ROUNDED FOR SUMMARY SHEET				3.2	9,815		736.2	390	390	390	2.9	9,815	

EROSION CONTROL ITEMS

LOCATION				EROSION CONTROL BLANKET	STONE DUMPED RIPRAP, CLASS A4	FILTER FABRIC	AGGREGATE DITCH
STATION	TO	STATION	LT/RT	M2510630	M2810707	M2820200	M2830400
				SQ. METER	SQ. METER	SQ. METER	M. TON
RURAL							
1+052.7	TO	1+055.9	LT		14.7	14.7	
1+052.7	TO	1+055.9	RT		11.7	11.7	
1+517.7	TO	1+522.3	LT		18.0	18.0	
1+517.7	TO	1+535.0	RT		92.2	92.2	
1+825.0	TO	1+884.8	LT	110.0	168.8	168.8	
1+825.0	TO	1+925.0	RT	190.0	262.3	262.3	
2+053.6	TO	2+142.6	RT	498.2			
2+142.6	TO	2+146.0	LT		16.9	16.9	
2+142.6	TO	2+146.0	RT		33.9	33.9	
2+146.0	TO	2+393.0	RT	1,333.7			
2+413.6	TO	2+698.0	RT	1,535.0			
2+698.0	TO	2+702.0	LT		14.4	14.4	
2+698.0	TO	2+756.0	RT		318.3	318.3	
				3,666.9	951.2	951.2	0.0
OBLONG							
2+755.0	TO	2+759.5	LT		14.7	14.7	
2+762.0	TO	2+773.8	RT		115.5	115.5	
3+960.0	TO	3+963.0	LT		15.3	15.3	
				0.0	145.5	145.5	0.0
RURAL							
4+473.6	TO	4+478.8	LT		27.5	27.5	
4+473.6	TO	4+478.8	RT		31.2	31.2	
4+478.8	TO	4+574.1	LT			223.5	119.6
4+592.8	TO	4+610.4	LT			42.8	22.9
4+478.8	TO	4+520.0	RT			100.4	53.7
4+538.0	TO	4+590.2	RT			127.1	68.0
4+612.5	TO	4+634.2	RT			52.9	28.3
				0.0	58.7	605.4	292.5
TOTAL				3,666.9	1,155.4	1,702.1	292.5
TOTALS ROUNDED FOR SUMMARY SHEET				3,667	1,156	1,703	293

PERIMETER EROSION BARRIER

LOCATION	METER
RURAL	
0+950 TO 1+050 LT	100
TOTAL	100

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p>SCALE NO SCALE DRAWN BY KOJ</p> <p>DATE FEBRUARY 6, 2009 CHECKED BY LWJ</p>

PLOT DATE = 2/6/2009
FILE NAME = H:\4428\Contract 74349\SHIT_014_sch.dwg

H. M. & G. NO. 4420