

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM SEWER SCHEDULE (CONTINUED)

UPSTREAM STRUCTURE				DOWNSTREAM STRUCTURE				PRECAST REINFORCED CONCRETE FLARED END SECTIONS		REINFORCED CONCRETE PIPE TEE						JUNCTION BOX NO.1	PRECAST CONCRETE BOX CULVERT, 1.5M x 0.6M	BOX CULVERT END SECTION, CULVERT NO. 7
STR #	LOCATION			STR #	LOCATION			600MM	1050MM	300MM PIPE WITH 300MM RISER	450MM PIPE WITH 300MM RISER	600MM PIPE WITH 300MM RISER	750MM PIPE WITH 300MM RISER	900MM PIPE WITH 300MM RISER	1050MM PIPE WITH 300MM RISER	60247400	MX540110	54001007
	STATION	OFFSET	LT/RT		STATION	OFFSET	LT/RT	M542E128	M542E148	M542C212	M542C220	M542C228	M542C236	M542C244	M542C248			
EX	4+379.915	9.016	LT	526	4+403.640	7.860	LT											
526	4+403.640	7.860	LT	527	4+403.640	4.475	RT											
527	4+403.640	4.475	RT	528	4+403.640	6.200	RT											
529	4+451.600	4.475	RT	530	4+451.600	11.000	RT											
TOTALS								2.000	1.000	1.000	2.000	8.000	5.000	7.000	3.000	1.000	64.400	1.000
TOTALS ROUNDED FOR SUMMARY SHEET								2	1	1	2	8	5	7	3	1	64.4	1

PLOT DATE = 2/6/2009
 FILE NAME = H:\4420\Contract 74349\SHI_031_sch_stormsewer_v8.dgn

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		STORM SEWER SCHEDULE SCALE _____ DRAWN BY KOJ DATE FEBRUARY 6, 2009 CHECKED BY LWJ

H. M. & G. NO. 4420