

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	40
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

RURAL ENTRANCE SCHEDULE

LOCATION				WIDTH	LENGTH			RADIUS	AGGREGATE BASE COURSE, TYPE B	HOT-MIX ASPHALT BASE COURSE	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE (PRIME COAT)	INCIDENTAL HOT-MIX ASPHALT SURFACING		PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT	
												PRIOR TO BINDER/BASE COURSE	PRIOR TO SURFACE COURSE		50MM	75MM		200 MM
STATION	LT/RT	TYPE	EXISTING MATERIAL	W1	L1	L2		150MM	200MM	150MM								
				METER	METER	METER	METER	M3511010	M3550500	M4021010	M4080100	M4080300	M4080500	M4230200				
								M TON	SQ. M	M TON	LITER	LITER	M TON	M TON	M TON	SQ. M		
RURAL																		
STA 0+952.000	RT	PE	AGGREGATE	4.6	6.30	2.54	6	12.68		4.21		52.82			6.34			
STA 1+201.500	LT	FE	DIRT	3.7	6.30	2.54	6			9.86								
STA 1+392.000	LT	CE	CONC/AGG	9.3	6.30	3.62	6			12.12					77.64			
STA 1+465.000	LT	FE	DIRT	5.5	6.30	3.82	6			16.56								
STA 1+465.000	RT	FE	DIRT	5.5	6.30	3.82	6			16.56								
STA 1+595.600	RT	FE	AGGREGATE	5.2	6.30	6.28	6			18.61								
STA 1+755.200	LT	PE	AGGREGATE	5.5	6.30	7.11	6	14.41		14.08		60.06			7.21			
STA 1+764.500	RT	FE	DIRT	7.2	9.30	4.11	9			33.42								
STA 1+970.300	RT	ROAD	AGGREGATE	5.5	See Plans	See Plans	10		236.98		355.47	82.94	0.355	28.44				
STA 1+970.300	RT	PE	AGGREGATE	See Plans	See Plans	See Plans	3	10.90		65.55		45.40			5.45			
STA 2+196.000	LT	FE	DIRT	3.6	6.30	8.64	6			17.52								
STA 2+403.300	RT	CE	CONCRETE	7.2	12.30	7.19	12									209.33		
STA 2+534.000	LT	FE	DIRT	4.3	6.30	7.11	6			18.33								
STA 2+575.600	LT	PE	AGG/BIT	5.2	6.30	7.11	6	27.16				113.16			13.58			
STA 2+759.000	RT	FE	DIRT	3.6	6.30	11.04	6			20.63								
OBLONG - SEE URBAN ENTRANCE SCHEDULE FOR OBLONG																		
STA 4+529.000	RT	PE	OIL & CHIP	7.2	9.30	5.64	9	45.95				191.45			22.97			
STA 4+583.500	LT	PE	AGGREGATE	7.2	9.30	5.64	9	31.34		14.61		130.57			15.67			
STA 4+601.300	RT	CE	AGGREGATE	10.6	9.30	5.52	9		115.61	21.06	173.41	40.46	0.173	13.87				
STA 4+618.800	LT	PE	AGGREGATE	4.7	9.30	5.74	9	23.78		9.71		99.07			11.89			
TOTALS								166.21	352.59	292.85	528.88	815.93	0.53	42.31	83.10	286.97		
TOTALS ROUNDED FOR SUMMARY SHEET								167	353	293	1,345	1	126	287				

PLOT DATE = 2/6/2009
FILE NAME = H:\4420\Contract 74349\SHIT_040_ent_2_V8.dgn

H. M. & G. NO. 4420

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">RURAL ENTRANCE SCHEDULE</p> <p>SCALE NO SCALE DRAWN BY KOJ</p> <p>DATE FEBRUARY 6, 2009 CHECKED BY LWJ</p>