

RESURFACING SCHEDULE

STATION TO STATION	LENGTH FOOT	AVERAGE PAVEMENT WIDTH FOOT	AREA SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" SQ YD	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", NTO, 1 1/2" TON	AGGREGATE SHOULDERS, TYPE B TON	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT SQ YD	TEMPORARY RAMP SQ YD
0+10.00 TO 0+90.00	80.0	VAR.	884.0	0.0	884.0	88.4	1.8	74.3	0.0	0.0	92.2
0+90.00 TO 3+19.00	229.0	32.0	814.2	814.2	0.0	81.4	1.6	68.4	17.4	0.0	0.0
3+19.00 TO 190+00.00	18681.0	26.0	53967.3	53967.3	0.0	5396.7	107.9	4533.3	1325.7	0.0	0.0
190+00.00 TO 196+30.00	630.0	32.0	2240.0	2240.0	0.0	224.0	4.5	188.2	0.0	0.0	0.0
196+30.00 TO 529+50.00	33320.0	26.0	96257.8	96257.8	0.0	9625.8	192.5	8085.7	2312.7	0.0	0.0
529+50.00 TO 532+44.00	294.0	36.0	1176.0	1176.0	0.0	117.6	2.4	98.8	19.6	0.0	0.0
532+44.00 TO 687+80.00	15536.0	26.0	44881.8	44881.8	0.0	4488.2	89.8	3770.1	1115.3	0.0	0.0
687+80.00 TO 688+10.00	30.0	26.0	86.7	0.0	0.0	8.7	0.2	7.3	2.3	86.7	14.4
MBT'S AND FE APRONS	0.0	0.0	0.0	0.0	0.0	0.0	0.0	112.5	0.0	0.0	0.0
TOTALS			200308.0	199337.0	884.0	20031.0	401.0	16939.0	4793.0	87.0	107.0

SURVEY MONUMENT SCHEDULE

STATION	OFFSET FOOT	PERMANENT SURVEY MARKERS TO BE ADJUSTED EACH	SURVEY MARKER VAULT EACH	SURVEY MONUMENT COVER ASSEMBLY EACH
26+49	0.4 LT		1.0	1.0
53+07	7.0 RT	1.0		
159+23	6.9 RT		1.0	1.0
185+73	2.0 RT	1.0		
212+21	6.6 LT		1.0	1.0
265+26	4.2 LT		1.0	1.0
291+70	0.8 LT		1.0	1.0
318+14	1.4 RT		1.0	1.0
344+53	0.3 LT		1.0	1.0
370+91	3.2 LT		1.0	1.0
423+70	0.0		1.0	1.0
423+70	2.8 RT		1.0	1.0
450+13	0.5 RT	1.0		
476+59	5.3 RT	1.0		
502+97	2.7 RT		1.0	1.0
529+28	0.0		1.0	1.0
529+28	14.5 RT		1.0	1.0
634+22	0.4 LT		1.0	1.0
TOTALS		4.0	14.0	14.0

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH FOOT	PAINT PAVEMENT MARKING - LINE 4" FOOT	PAINT PAVEMENT MARKING - LINE 6" FOOT	PAINT PAVEMENT MARKING - LINE 12" FOOT	PAINT PAVEMENT MARKING - LINE 24" FOOT	TEMPORARY PAVEMENT MARKING - LINE 4" FOOT	SHORT-TERM PAVEMENT MARKING FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	RAISED REFLECTIVE PAVEMENT MARKER EACH
0+10.00 TO 494+50.00	49440.0	109191.0	155.0	73.0	30.0	109191.0	9888.0	1648.0	618.0
494+50.00 TO 502+15.00	765.0	2486.3	0.0	0.0	0.0	2486.3	152.0	25.3	10.0
502+15.00 TO 505+90.00	375.0	843.8	0.0	0.0	0.0	843.8	72.0	12.0	5.0
505+90.00 TO 513+35.00	745.0	2297.3	0.0	0.0	0.0	2297.3	152.0	25.3	9.0
513+35.00 TO 688+10.00	17475.0	38877.8	0.0	0.0	0.0	38877.8	3496.0	582.7	218.0
TOTALS		153696.0	155.0	73.0	30.0	153696.0	13760.0	2293.0	860.0

Partial Depth Removal(SQ YDS)

Northbound	467
Southbound	632
Totals	1099

Partial Depth Patching(TONS)

Northbound	275
Southbound	371
Totals	646