

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	177	177	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8533	8533	
40600300	AGGREGATE (PRIME COAT)	TON	171	171	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3584	3584	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	650	650	
40600990	TEMPORARY RAMP	SQ YD	217	217	
40600995	TEMPORARY RAMP, SPECIAL	SQ YD	728	728	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	7167	7167	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	100	100	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	61348	61348	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	12876	12876	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	11103	11103	
44200132	PAVEMENT PATCHING, TYPE II, 11 INCH	SQ YD	36	36	
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SQ YD	35	35	
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	852	852	
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	149	149	
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	25	25	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3172	3172	
66700095	PERMANENT SURVEY MARKERS	EACH	33	33	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10412	10412	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	90	90	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	80986	80986	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	256	256	

SUMMARY OF QUANTITIES			100% FED. TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	255	255	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	868	868	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	90	90	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9843	9843	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	256	256	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	255	255	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	71143	71143	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	383	383	
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	1	1	

**specialty items*

FILE NAME =	USER NAME = steffernk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwork\pwork\steffernk\d0123229\07	74379-ahf-soq.dgn	DRAWN -	REVISED -			773		Cumberland	26	3
	PLOT SCALE = 20,0000' / IN.	CHECKED -	REVISED -							
	PLOT DATE = 2/6/2009	DATE -	REVISED -							
						SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.
						ILLINOIS FED. AID PROJECT CONTRACT NO. 74379				