

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FRANKLIN CO.
				ROADWAY RURAL 100% FED
CONSTRUCTION TYPE CODE				1000
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	7	7
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4	4
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	8
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	2	2
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	13	13
63200310	GUARDRAIL REMOVAL	FOOT	13,415	13,415
63500105	DELINEATORS	EACH	60	60
63500120	DELINEATOR REMOVAL	EACH	60	60
64200105	SHOULDER RUMBLE STRIP	FOOT	88,311	88,311
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3	3
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	50
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,687	3,687
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1,229	1,229
* 72000100	SIGN PANEL - TYPE I	SO FT	266	266
* 72900110	METAL POST - TYPE A	EACH	24	24
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	92,799	92,799
* 78003135	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 6", SPECIAL	FOOT	11,530	11,530
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	2,110	2,110
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	677	677
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	112	112
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	13	13
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	677	677
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	400	400

* SPECIALTY ITEMS

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pv_work\pvd\dot\colemm\d0115620\d978112_sht_miso.dgn		DRAWN -	REVISED -		57	.	FRANKLIN	47	9
PLOT SCALE = 103.6758' / IN.		CHECKED -	REVISED -		CONTRACT NO. 78112				
PLOT DATE = 2/4/2009		DATE -	REVISED -		ILLINOIS FED. AID PROJECT				
					SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.