

SCHEDULE OF QUANTITIES

SHEET 4 OF 9

63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

STATION	TO	STATION	QUANTITY (FT)
S.N. 092-8311			
LT	860+95.50	861+45.50	50.00
RT	859+70.50	860+20.50	50.00
TOTAL			100.00 FOOT

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

STATION	TO	STATION	QUANTITY (FT)
S.N. 092-8311			
LT	860+20.50	860+45.50	25.00
LT	860+70.50	860+95.50	25.00
RT	860+20.50	860+45.50	25.00
RT	860+70.50	860+95.50	25.00
TOTAL			100.00 FOOT

Z0055300 RUMBLE STRIP

STATION	QUANTITY (EACH)	
LT 631+15.00	1.00	
LT 816A+97.10	1.00	
LT 818A+97.10	1.00	
LT 825+97.10	1.00	
TOTAL		4.00 EACH

63000025 STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES

STATION	TO	STATION	QUANTITY (FT)
S.N. 092-8311			
LT	860+45.50	860+70.50	25.00
RT	860+45.50	860+70.50	25.00
TOTAL			50.00 FOOT

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT

STATION	TO	STATION	QUANTITY (EACH)
S.N. 092-8311			
LT	859+70.50	860+20.50	1.00
LT	861+45.50	861+95.50	1.00
RT	859+20.50	859+70.50	1.00
RT	860+95.50	861+45.50	1.00
TOTAL			4.00 EACH

Z0070100 SURVEY MONUMENT COVER ASSEMBLY

STATION	QUANTITY (EACH)	
789+56.90	1.00	
816+08.60	1.00	
921+31.50	1.00	
974+71.00	1.00	
TOTAL		4.00 EACH

ISLAND REPLACEMENT

LOCATION			44000500 COMB. CONC. C&G REMOVAL (FOOT)	44002020 CONCRETE MEDIAN SURFACE REMOVAL (SQ FT)	35300500 PCB BASE COURSE 10" (SQ YD)	60622354 CONCRETE MED TYPE SM-6 DOWELLED (SQ FT)
LT	814A+20	IL 119 / BISMARCK INT.	33.00	40.00	6.00	140.00
TOTAL =			33.00	40.00	6.00	140.00

* THE TOP OF THE BASE COURSE SHALL BE PLACED FLUSH WITH THE TOP OF EXISTING PAVEMENT. IT IS TO BE OVERLAID AT THE SAME TIME AS THE ADJACENT PAVEMENT PRIOR TO CONSTRUCTION OF THE DOWELLED MEDIAN. THE REMOVAL AND RE-INSTALLATION OF THE STOP SIGN AND POSTS WILL BE INCIDENTAL TO THE CONCRETE MEDIAN, TYPE SM-6 DOWELLED.