

SCHEDULE OF QUANTITIES

SHEET 7 OF 9

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
814A+35.00		817A+85.00	DBL DBL	1,400.0	YELLOW
TOTAL =				1,400.0 FT	

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
869+16.00			RXR CROSSING	78.0	WHITE
BISMARCK RD			STOP BAR	14.0	WHITE
BISMARCK RD			STOP BAR	18.0	WHITE
ALVIN SPUR			STOP BAR	13.0	WHITE
ALVIN CONNECTOR			STOP BAR	21.0	WHITE
ALVIN CONNECTOR			STOP BAR	20.0	WHITE
TOTAL =				164.0 FT	

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
814A+35.00			ISLAND	133.0	WHITE
TOTAL =				133.0 FT	

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

STATION	LOCATION	QUANTITY (SQ FT)	COLOR
869+16.00	RXR CROSSING	123	WHITE
TOTAL =		123 SQ FT	

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

STATION	TO	STATION	LOCATION	QUANTITY (FT)	COLOR
814A+35.00			ISLAND	79.0	WHITE
TOTAL =				79.0 FT	

44201789 CLASS D PATCHES, TYPE II, 12 INCH

STATION	DIRECTION	LOCATION	LENGTH (FT)	WIDTH (FT)	PATCH AREA (SQ YD)
766+60.00	EASTBOUND	MAINLINE	10.00	10.00	11.11
766+60.00	WESTBOUND	MAINLINE	10.00	10.00	11.11
TOTAL =					22.22
USE					22.00 (SQ YD)