ROUTE: IL 31 (Johnsberg Rd. to US 12)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PVT MKS
Johnsburg Rd.	Ringwood Rd.	NB	1	12	6	72	8			8				
Johnsburg Rd.	Ringwood Rd.	NB	1	12	6	72	8			8				
Johnsburg Rd.	Ringwood Rd.	NB	1	12	6	72	8			8				
Johnsburg Rd.	Ringwood Rd.	NB	1	12	6	72	8			8				
Johnsburg Rd.	Ringwood Rd.	NB	1	12	6	72	8			8				
Johnsburg Rd.	Ringwood Rd.	SB	1	12	6	72	8			8				
Johnsburg Rd.	Ringwood Rd.	SB	1	12	6	72	8			8				
Johnsburg Rd.	Ringwood Rd.	SB	1	12	6	72	8			8				
Johnsburg Rd.	Ringwood Rd.	SB	1	12	50	600	67	67						
Johnsburg Rd.	Ringwood Rd.	SB	1	3	100	300	33	33						
Johnsburg Rd.	Ringwood Rd.	SB	1	12	8	96	11			11				
Ringwood Rd.	Harts Rd.	NB	1	12	6	72	8			8				
Ringwood Rd.	Harts Rd.	NB	1	12	6	72	8			8				
Ringwood Rd.	Harts Rd.	NB	1	12	6	72	8			8				
Ringwood Rd.	Harts Rd.	NB	1	12	6	72	8			8				
Ringwood Rd.	Harts Rd.	NB	1	12	6	72	8			8				
Ringwood Rd.	Harts Rd.	NB	1	12	6	72	8			8				
Ringwood Rd.	Harts Rd.	NB	1	12	6	72	8			8				
Ringwood Rd.	Harts Rd.	NB	1	12	6	72	8			8				
Ringwood Rd.	Harts Rd.	SB	1	12	8	96	11			11				
Ringwood Rd.	Harts Rd.	SB	1	6	25	125	14	14						
Ringwood Rd.	Harts Rd.	Centerline		3	100	300	33	33						
Ringwood Rd.	Harts Rd.	Centerline		3	250	750	83	83						
Ringwood Rd.	Harts Rd.	SB	1	12	100	1200	133	133						
Ringwood Rd.	Harts Rd.	Centerline		3	50	150	17	17						
Ringwood Rd.	Harts Rd.	SB	1	12	75	900	100	100						
Ringwood Rd.	Harts Rd.	Centerline		3	50	150	17	17						
Ringwood Rd.	Harts Rd.	Centerline		3	100	300	33	33						
Ringwood Rd.	Harts Rd.	SB	1	12	100	1200	133	133						
Ringwood Rd.	Harts Rd.	SB	1	3	100	300	33	33						
Ringwood Rd.	Harts Rd.	SB	1	12	50	600	67	67						
Harts Rd.	IL Rt. 12	NB	1	12	6	72	8			8				
Harts Rd.	IL Rt. 12	NB	1	12	6	72	8			8				
Harts Rd.	IL Rt. 12	NB	1	12	6	72	8			8				
Harts Rd.	IL Rt. 12	NB	1	12	6	72	8			8				
Harts Rd.	IL Rt. 12	SB	1	12	6	72	8			8				
Harts Rd.	IL Rt. 12	SB	1	12	6	72	8			8				
Harts Rd.	IL Rt. 12	SB	1	12	6	72	8			8				
Harts Rd.	IL Rt. 12	SB	1	12	6	72	8			8				
Harts Rd.	IL Rt. 12	SB	1	12	125	1500	167	167						
Harts Rd.	IL Rt. 12	Centerline		3	75	225	25	25						
Harts Rd.	IL Rt. 12	Centerline		3	500	1500	167	167						
Harts Rd.	IL Rt. 12	NB	1	12	75	900	100	100						
Harts Rd.	IL Rt. 12	Centerline		3	75	225	25	25						
Harts Rd.	IL Rt. 12	NB	1	12	20	240	27	27						
Harts Rd.	IL Rt. 12	NB	1	12	15	180	20				20			
Harts Rd.	IL Rt. 12	NB	1	12	15	180	20				20			
Harts Rd.	IL Rt. 12	Centerline		3	100	300	33	33						
		TOTALS:					1561 SY	1307 SY		214 SY	40 SY		FT	EACH

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS C PATCH TYPE I	CLASS C PATCH TYPE II	CLASS C PATCH TYPE III	CLASS C PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PVT MKS
Crystal Lake														
Rakow Rd.	Three Oaks Rd.													
PCC PAVT SECTION		SB	2	6	15	90	10			10				
		NB	1	12	6	72	8			8				
		SB	2	12	8	96	11			11				
		NB	1	12	15	180	20				20			
		NB	2	12	15	180	20				20			
		SB	1	12	15	180	20				20			
		SB	2	12	15	180	20				20			
		TOTALS:					109 SY			29 SY	80 SY		FT	EACH

FILE NAME = c:\projects\d136180\design_ea.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/14/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 31

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-010 PP	MCHENRY	27	12
		CONTRACT NO. 60E36		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT