ROUTE: Grand Ave (Mt Prospect Rd to Mannhiem Rd)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
NW Ave (con't)		EB	2	12	40	480	53	53						
		EB	2	12	10	120	13			13				
		EB	2	3	5	15	2		2					
		EB	2	3	5	15	2		2					
		EB	2	1.5	60	90	10			10				
		EB	2	6	4	24	3		3					
		EB	2	6	8	48	5		5					
		EB	2	8	30	240	27					27		
		EB	2	5	5	25	3		3					
		EB	2	6	4	24	3		3					
	Wolf Rd	EB	1	4	4	16	2		2					
Wolf Rd		EB	2	12	40	480	53	53						
		EB	1	4	10	40	4		4					
		EB	2	12	4	48	5		5					
		EB	2	4	3	12	1		1					
		EB	1	3	8	24	3		3					
		EB	1	2	2	4	0							
		EB	2	2	8	16	2		2					
		EB	1	2	2	4	0							
		EB	1	3	4	12	1		1					
		EB	2	3	60	180	20				20			
		EB	1	2	2	4	0							
Wolf Rd (con't)		EB	2	3	4	12	1		1					
		EB	2	6	6	36	4		4					
		EB	2	3	5	15	2		2					
		EB	2	3	60	180	20				20			
		EB	2	3	3	9	1		1					
		EB	2	3	3	9	1		1					
		EB	2	3	3	9	1		1					
		EB	2	4	20	80	9			9				
		EB	1	2	5	10	1		1					
		EB	1	12	15	180	20				20			
		EB	2	3	3	9	1		1					
		EB	1	5	15	75	8			8				
		EB	1	3	8	24	3		3					
		EB	1	3	150	450	50	50						
		EB	2	12	10	120	13			13				
		EB	1	3	200	600	67	67						
		EB	2	5	4	20	2		2					
		EB	1	3	100	300	33					33		
Wolf Rd (con't)		EB	2	6	20	120	13			13				
		EB	1	3	3	9	1		1					
		EB	2	8	10	80	9			9				
		EB	2	8	8	64	7			7				
		EB	2	2	2	4	0							
		EB	1	2	2	4	0							
		EB	2	2	2	4	0							
		EB	2	6	10	60	7			7				
		EB	2	3	40	120	13			13				
		EB	1	2	3	6	1		1					
		EB	2	12	5	60	7			7				
		EB	1	4	10	40	4		4					
		EB	1	3	30	90	10			10				
		EB	2	3	4	12	1		1					
		EB	2	12	8	96	11			11				
		EB	2	6	4	24	3		3					
		EB	1	5	10	50	6			6				
		EB	2	6	20	120	13			13				
Wolf Rd (con't)		EB	2	6	15	90	10			10				
		EB	2	6	8	48	5		5					
		EB	2	6	3	18	2		2					
		EB	2	5	6	30	3		3					
		EB	1	3	80	240	27					27		
		EB	2	2	60	120	13			13				
		EB	1	3	50	150	17				17			
		EB	2	45	15	675	75	75						
	Mannhiem Rd	EB	1		60	0	0							
		Total					2068 SY	879 SY	227 SY	476 SY	252 SY	231 SY	1700 FT	85 EACH

FILE NAME = c:\projects\d136508\design_aa.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE GRAND AVE.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-014 PP	COOK	84 / 35
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E40	
	PLOT DATE = 3/13/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	