ROUTE: Montrose Ave (Forest Preserve Rd to Narrqgansett Ave)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Forest Preserve Rd.	Neenah Rd.	EB	1, 2	1.5	25	38	4		4					
Forest Preserve Rd.	Neenah Rd.	EB	2	5	5	25	3		3					
Forest Preserve Rd.	Neenah Rd.	EB	1	3	200	600	67	67						
Forest Preserve Rd.	Neenah Rd.	EB	2	12	160	1920	213	213						
Forest Preserve Rd.	Neenah Rd.	EB	1, 2	3	40	120	13			13				
Forest Preserve Rd.	Neenah Rd.	EB	1	3	40	120	13			13				
Neenah Rd.	Narragansett Ave.	EB	2	12	160	1920	213	213						
Neenah Rd.	Narragansett Ave.	EB	2	12	100	1200	133	133						
Neenah Rd.	Narragansett Ave.	EB	2	12	200	2400	267	267						
Neenah Rd.	Narragansett Ave.	EB	1	12	200	2400	267	267						
Neenah Rd.	Narragansett Ave.	EB	2	4	100	400	44	44						
Narragansett Ave	Neenah Ave.	WB	2	12	100	1200	133	133						
Narragansett Ave	Neenah Ave.	WB	1	3	100	300	33					33		
Narragansett Ave	Neenah Ave.	WB	2	3	20	60	7			7				
Narragansett Ave	Neenah Ave.	WB	1, 2	3	150	450	50	50						
Narragansett Ave	Neenah Ave.	WB	1	2	2	4	0							
Neenah Ave.	Forest Preserve Rd.	WB	1	12	70	840	93	93						
Neenah Ave.	Forest Preserve Rd.	WB	1	12	2	24	3		3					
Neenah Ave.	Forest Preserve Rd.	WB	1, 2	1.5	100	150	17				17			
Neenah Ave.	Forest Preserve Rd.	WB	1	12	12	144	16				16			
Neenah Ave.	Forest Preserve Rd.	WB	2	3	3	9	1		1					
		Total					1592 SY	1480 SY	11 SY	33 SY	33 SY	33 SY	800 FT	40 EACH

FILE NAME = c:\projects\d136508\design_ab.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE MONTROSE AVE.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-014 PP	COOK	84	60
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E40		
	PLOT DATE = 3/13/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		