ROUTE: IL 50/Cicero Ave (Cities Service Dr to 31st St) SB

CROSS FROM	STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
31st	Cities service drive	sb	3	2	4	8	1		1					
31st	Cities service drive	sb	2	3	3	8	1		1					
31st	Cities service drive	sb	2	3	3	6	1		1					
31st	Cities service drive	sb	1	2	6	12	1		1					
31st	Cities service drive	sb	1	2	2	4	0							
31st	Cities service drive	sb	2	1	1	1	0							
31st	Cities service drive	sb	3	3	4	10	1		1					
31st	Cities service drive	sb	3	4	4	16	2		2					
31st	Cities service drive	sb	3	4	4	16	2		2					
31st	Cities service drive	sb	3	1	3	3	0							
31st	Cities service drive	sb	2	1	3	3	0							
31st	Cities service drive	sb	3	1	12	12	1		1					
31st	Cities service drive	sb	3	2	3	5	1		1					
31st	Cities service drive	sb	3	2	3	5	1		1					
31st	Cities service drive	sb	3	2	6	12	1		1					
31st	Cities service drive	sb	3	2	2	2	0							
31st	Cities service drive	sb	1	2	3	6	1		1					
31st	Cities service drive	sb	3	3	5	15	2		2					
31st	Cities service drive	sb	3	2	4	8	1		1					
31st	Cities service drive	sb	3	2	4	8	1		1					
31st	Cities service drive	sb	2	1	5	5	1		1					
31st	Cities service drive	sb	3	1	3	3	0							
31st	Cities service drive	sb	3	1	3	3	0							
31st	Cities service drive	sb	3	3	3	9	1		1					
31st	Cities service drive	sb	3	4	4	16	2		2					
31st	Cities service drive	sb	3	4	4	16	2		2					
31st	Cities service drive	sb	3	2	2	4	0							
31st	Cities service drive	sb	3	1	3	3	0							
31st	Cities service drive	sb	3	2	5	10	1		1					
31st	Cities service drive	sb	3	2	4	8	1		1					
31st	Cities service drive	sb	3	3	4	10	1		1					
31st	Cities service drive	sb	3	3	4	10	1		1					
31st	Cities service drive	sb	3	2	4	8	1		1					
31st	Cities service drive	sb	2	1	5	5	1		1					
31st	Cities service drive	sb	3	1	3	3	0							
31st	Cities service drive	sb	3	1	3	3	0							
31st	Cities service drive	sb	3	3	3	9	1		1					
31st	Cities service drive	sb	3	4	4	16	2		2					
31st	Cities service drive	sb	3	4	4	16	2		2					
31st	Cities service drive	sb	3	2	2	4	0							
31st	Cities service drive	sb	3	1	3	3	0							
31st	Cities service drive	sb	3	2	5	10	1		1					
31st	Cities service drive	sb	3	2	4	8	1		1					
31st	Cities service drive	sb	3	3	4	10	1		1					
31st	Cities service drive	sb	3	3	4	10	1		1					
		Total					576 SY	67 SY	268 SY	163 SY	22 SY	54 SY	700 FT	35 EACH

FILE NAME = c:\projects\d136608\design_aadgn	USER NAME = smithAJ	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE IL 50 (CICERO)	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-015 PP	COOK	75	20
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E41		
	PLOT DATE = 3/14/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		