ROUTE: Cicero Ave (43rd St to 79th St)

CROSS STREETS FROM	TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR\ AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
43rd	79th	SB	3	2	2	4	0							
43rd	79th	SB	3	1	2	2	0							
43rd	79th	SB	3	10	10	100	11			11				
43rd	79th	SB	M	1	1	1	0							
43rd	79th	SB	M	1	1	1	0							
43rd	79th	SB	2	1	1	1	0							
43rd	79th	SB	3	2	1	2	0							
43rd	79th	SB	3	2	3	6	1		1					
43rd	79th	SB	2	2	2	4	0							
43rd	79th	SB	2	2	4	8	1		1					
43rd	79th	SB	2	2	2	4	0							
43rd	79th	SB	3	1	2	2	0							
43rd	79th	SB	2	1	1	1	0							
43rd	79th	SB	2	1	1	1	0							
43rd	79th	SB	1	1	1	1	0							
43rd	79th	SB	2	1	1	1	0							
43rd	79th	SB	2	3	2	6	1		1					
43rd	79th	SB	3	1	3	3	0							
43rd	79th	SB	3	3	3	9	1		1					
43rd	79th	SB	2	1	1	1	0							
43rd	79th	SB	1	1	1	1	0							
43rd	79th	SB	1	1	1	1	0							
43rd	79th	SB	3	2	2	4	0							
43rd	79th	SB	3	1	1	1	0							
43rd	79th	SB	1	1	1	1	0							
43rd	79th	SB	2	1	1	1	0							
43rd	79th	SB	1	1	1	1	0							
43rd	79th	SB	1	1	1	1	0							
43rd	79th	SB	1	1	1	1	0							
43rd	79th	SB	3	1	1	1	0							
43rd	79th	SB	2	1	1	1	0							
43rd	79th	SB	1	1	1	1	0							
43rd	79th	SB	2	2	2	2	0							
43rd	79th	SB	2	1	1	1	0							
43rd	79th	SB	3	1	1	1	0							
43rd	79th	SB	1	1	1	1	0							
43rd	71ST	SB	3	1	1	1	0							
43rd	71ST	SB	3	1	3	3	0							
43rd	71ST	SB	2	1	1	1	0							
43rd	71ST	SB	3	1	1	1	0							
43rd	71ST	SB	2	3	3	9	1		1					
43rd	71ST	SB	1	1	3	3	0							
43rd	71ST	SB	2	1	1	1	0							
43rd	71ST	SB	2	1	2	2	0							
43rd	71ST	SB	3	1	3	3	0							
43rd	71ST	SB	1	1	1	1	0							
43rd	71ST	SB	3	1	1	1	0							
43rd	71ST	SB	3	1	1	1	0							
43rd	71ST	SB	1	1	1	1	0							
43rd	71ST	SB	2	2	4	8	1		1					
43rd	71ST	SB	2	4	4	16	2		2					
43rd	71ST	SB	2	2	2	4	0							
43rd	71ST	SB	1	1	1	1	0							
43rd	71ST	SB	3	1	1	1	0							
43rd	71ST	SB	3	1	1	1	0							
43rd	71ST	SB	2	2	3	6	1		1					
43rd	71ST	SB	2	2	12	24	3		3					
43rd	71ST	SB	2	4	4	16	2		2					
43rd	71ST	SB	2	4	4	16	2		2					
43rd	71ST	SB	2	2	3	6	1		1					
43rd	71ST	SB	2	2	3	6	1		1					

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\d136608\design_ae.dgn
USER NAME = smithkl
PLOT SCALE = 103.7851 ' / IN.
PLOT DATE = 3/14/2008
DESIGNED -
DRAWN -
CHECKED -
DATE -
REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
CICERO AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-015 PP	COOK	75	28

CONTRACT NO. 60E41

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT