ROUTE: Cicero Ave (43rd St to 79th St)

CROSS FROM	STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR\ AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
43rd	79th	SB	2	1	1	1	0							
43rd	79th	SB	3	2	5	10	1		1					
43rd	79th	SB	2	1	5	5	1		1					
43rd	79th	SB	1	1	6	6	1		1					
43rd	79th	SB	3	2	3	6	1		1					
43rd	79th	SB	3	2	4	8	1		1					
71ST	43RD	NB	2	2	2	4	0							
71ST	43RD	NB	3	1	1	1	0							
71ST	43RD	NB	2	1	3	3	0							
71ST	43RD	NB	3	2	3	6	1		1					
71ST	43RD	NB	3	2	3	6	1		1					
71ST	43RD	NB	3	2	2	4	0							
71ST	43RD	NB	3	1	2	2	0							
71ST	43RD	NB	1	2	3	6	1		1					
71ST	43RD	NB	1	1	4	4	0							
71ST	43RD	NB	3	1	3	3	0							
71ST	43RD	NB	2	2	3	6	1		1					
71ST	43RD	NB	3	1	3	3	0							
71ST	43RD	NB	2	1	3	3	0							
71ST	43RD	NB	2	1	3	3	0							
71ST	43RD	NB	2	1	1	1	0							
71ST	43RD	NB	2	1	12	12	1		1					
71ST	43RD	NB	2	1	1	1	0							
71ST	43RD	NB	1	4	4	16	2		2					
71ST	43RD	NB	3	3	12	36	4		4					
71ST	43RD	NB	1	3	8	24	3		3					
71ST	43RD	NB	1	4	8	32	4		4					
71ST	43RD	NB	1	2	2	4	0							
71ST	43RD	NB	1	3	6	18	2		2					
71ST	43RD	NB	1	1	12	12	1		1					
71ST	43RD	NB	1	2	2	4	0							
71ST	43RD	NB	2	2	6	12	1		1					
71ST	43RD	NB	1	1	4	4	0							
71ST	43RD	NB	2	3	8	24	3		3					
71ST	43RD	NB	1	2	4	8	1		1					
71ST	43RD	NB	3	1	1	1	0							
71ST	43RD	NB	2	2	3	6	1		1					
71ST	43RD	NB	2	2	2	4	0							
71ST	43RD	NB	3	2	2	4	0							
71ST	43RD	NB	2	1	6	6	1		1					
71ST	43RD	NB	1	2	2	4	0							
71ST	43RD	NB	3	2	12	24	3		3					
71ST	43RD	NB	2	3	12	36	4		4					
71ST	43RD	NB	2	1	4	4	0							
71ST	43RD	NB	3	2	2	4	0							
71ST	43RD	NB	3	2	2	4	0							
71ST	43RD	NB	1	2	2	4	0							
71ST	43RD	NB	3	1	1	1	0							
71ST	43RD	NB	3	2	4	8	1		1					
71ST	43RD	NB	3	2	2	4	0							
71ST	43RD	NB	3	2	12	24	3		3					
71ST	43RD	NB	2	2	12	24	3		3					
71ST	43RD	NB	3	2	12	24	3		3					
71ST	43RD	NB	2	1	1	1	0							
71ST	43RD	NB	2	1	2	2	0							
71ST	43RD	NB	3	1	4	4	0							
71ST	43RD	NB	2	1	3	3	0							
71ST	43RD	NB	2	1	1	1	0							
71ST	43RD	NB	2	1	1	1	0							
71ST	43RD	NB	3	1	1	1	0							
71ST	43RD	NB	2	3	3	9	1		1					
71ST	43RD	NB	2	1	12	12	1		1					
71ST	43RD	NB	3	2	6	12	1		1					
71ST	43RD	NB	1	2	2	4	0							
71ST	43RD	NB	2	2	2	4	0							
71ST	43RD	NB	2	1	2	2	0							
71ST	43RD	NB	2	1	6	6	1		1					
71ST	43RD	NB	1	2	3	6	1		1					

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\d136608\design.ae.dgn	USER NAME = smithkl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/14/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
CICERO AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-015 PP	COOK	75	30

CONTRACT NO. 60E41

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT