ROUTE: Cicero Ave (43rd St to 79th St)

CROSS STREETS FROM	TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR\ AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	1	1	3	3	0							
71ST	79TH	SB	1	1	3	3	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	2	2	2	4	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	3	3	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	3	3	0							
71ST	79TH	SB	2	1	2	2	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	4	4	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	3	3	0							
71ST	79TH	SB	1	2	4	8	1		1					
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	2	1	2	2	0							
71ST	79TH	SB	1	1	4	4	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	1	1	3	3	0							
71ST	79TH	SB	1	2	2	4	0							
71ST	79TH	SB	1	2	2	4	0							
71ST	79TH	SB	1	1	1	1	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	2	2	2	4	0							
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	2	1	2	2	0							
71ST	79TH	SB	2	1	8	8	1		1					
71ST	79TH	SB	1	1	2	2	0							
71ST	79TH	SB	2	2	6	12	1		1					
71ST	79TH	SB	2	1	1	1	0							
71ST	79TH	SB	3	2	6	12	1		1					
71ST	79TH	SB	3	2	2	4	0							

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\d136608\design_ea.dgn	USER NAME = smithkl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE CICERO AVE.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-015 PP	COOK	75 / 33
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E41	
	PLOT DATE = 3/14/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	