

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	5
STA.		TO STA.		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEMS	UNIT	URBAN	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	
			TOTAL	J000-2A	SFTY-3N	X02B-2A	X271-2A	Y007	Y030-1E	Y031-1F	Y077	Y079	SFTY-3C	Y002-1C
			QUANTITY	P. C. CONCRETE	IMPACT ATTN.	STRUCTURES	STRUCTURES	MINOR STRUCT.	HWY. LIGHTING	SIGNALS	WETLANDS	HAZ. WASTE	BREAKAWAY	TRAFFIC SIGNS
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	318	318										
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	216	216										
20100500	TREE REMOVAL, ACRES	ACRES	4.98	4.98										
20200100	EARTH EXCAVATION	C. Y.	82,287	57,165						25,122				
20400800	FURNISHED EXCAVATION	C. Y.	253,490	253,490										
20700220	POROUS GRANULAR EMBANKMENT	C. Y.	320				320							
20800150	TRENCH BACKFILL	C. Y.	2,589	2,589										
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	S. Y.	70,863	70,863										
21101625	TOPSOIL FURNISH AND PLACE, 6"	S. Y.	151,106	133,263						17,843				
25000310	SEEDING, CLASS 4	ACRE	3	3										
25000350	SEEDING, CLASS 7	ACRE	57	47						10				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5,315	4,395						920				
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	5,315	4,395						920				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5,315	4,395						920				
25000750	MOWING	ACRE	25.00	25.00										
25000775	SELECTIVE MOWING STAKES	EACH	12	12										
25000910	SEEDING, CLASS 1 (MODIFIED)	ACRE	40	40										
25001845	SEEDING, CLASS 7 (SPECIAL)	ACRE	10.22	10.22										
25100115	MULCH, METHOD 2	ACRE	114	104						10				
25100630	EROSION CONTROL BLANKET	S. Y.	3,094	3,094										
28000200	EARTH EXCAVATION FOR EROSION CONTROL	C. Y.	48	48										

△

REVISIED
2-23-05