

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE			
				URBAN													
				QUANTITY	J000-2A P. C. CONCRETE	SFTY-3N IMPACT ATTEN.	X028-2A STRUCTURES	X271-2A STRUCTURES	Y007 MINOR STRUCT.	Y030-1E HWY. LIGHTING	Y031-1F SIGNALS	Y077 WETLANDS	Y079 HAZ. WASTE	SFTY-3C BREAKAWAY	Y002-1C TRAFFIC SIGNS		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FT.	531	531													
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FT.	68	68													
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FT.	3,992	3,992													
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FT.	1,070	1,070													
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FT.	706	706													
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FT.	770	770													
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FT.	180	180													
55100500	STORM SEWER REMOVAL 12"	FT.	1,681	1,681													
55100700	STORM SEWER REMOVAL 15"	FT.	220	220													
55100900	STORM SEWER REMOVAL 18"	FT.	282	282													
55101200	STORM SEWER REMOVAL 24"	FT.	745	745													
55101600	STORM SEWER REMOVAL 36"	FT.	531	531													
*56103000	DUCTILE IRON WATER MAIN 6"	FT.	30	30													
*56103100	DUCTILE IRON WATER MAIN 8"	FT.	978	978													
*56103300	DUCTILE IRON WATER MAIN 12"	FT.	938	938													
*56105750	BUTTERFLY VALVES 12"	EACH	2	2													
*56201600	CORPORATION STOPS 1 1/2"	UNIT	1	1													
*56201800	CORPORATION STOPS 2"	EACH	3	3													
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1													
*56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	3	3													
*56400500	FIRE HYDRANTS TO BE REMOVED	EACH	6	6													

* SPECIALTY ITEMS