

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	16
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	93% STATE 7% CITY OF ROCK ISLAND	100% STATE	100% STATE	100% STATE
				J000 P. C. CONCRETE	SFTY-3N IMPACT ATTEN.	X028-2A STRUCTURES	X271-2A STRUCTURES	Y007 MINOR STRUCT.	Y030-1E HWY. LIGHTING	Y031-1F SIGNALS	Y031-1F	Y079 HAZ. WASTE	SFTY-3C BREAKAWAY	Y002-1C TRAFFIC SIGNS
*87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FT.	229								229			
*87301815	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 3C	FT.	484								359	125		
*87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	6								4	2		
*87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	2								1	1		
*87702880	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	2								1	1		
*87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2								1	1		
*87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1								1			
*87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	3								2	1		
*87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1								1			
*87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1								1			
*87800100	CONCRETE FOUNDATION, TYPE A	FT.	18								12	6		
*87800200	CONCRETE FOUNDATION, TYPE D	FT.	10.5								7	3.5		
*87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIA.	FT.	20								10	10		
*87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIA.	FT.	124								89	35		
*87900200	DRILL EXISTING HANDHOLE	EA.	1								1			
*88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLASTIC	EACH	43								30	13		
*88600100	DETECTOR LOOP, TYPE 1	FT.	376								376			
*89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1								1			
*89502380	REMOVE EXISTING HANDHOLE	EACH	1								1			
*89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1								1			

* SPECIALTY ITEMS