EARTHWORK SCHEDULES

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
44TH ST. CONNECTOR STAGE 1 PHASE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 0+50 - 6+00	1,495	1,121	899	222	1,570
TOTAL:	1,495	1,121	899	222	1,570

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
VALLEY VIEW STAGE 2 PHASE 3	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 152+50 - 171+29.12	12,438	9,329	3,573	5,756	15,219
TOTAL:	12,438	9,329	3,573	5,756	15,219

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
OLD BLACKHAWK ROAD STAGE 2 PHASE 3	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 0+15 - 1+85	783	587	45	542	458
TOTAL:	783	587	45	542	458

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
TRINITY DRIVE STAGE 1 PHASE 1	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA. 0+50 - 2+92.62	1,278	959	68	891	808
TOTAL:	1,278	959	68	891	808

LOCATION	EARTH	EARTH EXCAVATION	EMBANKMENT	EARTHWORK	TOPSOIL
	EXCAVATION	ADJUSTED FOR		BALANCE WASTE (+)	FURNISH AND
e e e e		SHRINKAGE (25%)		OR SHORTAGE (-)	PLACE,6"
		1.1	:		
THIRD STREET STAGE 1 PHASE 1	(C.Y _i .)	, (C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
LT & RT STA, 1+30 - 11+50	3,002	2,252	5,094	-2,843	6,977
THIRD STREET STAGE 1 PHASE 2					
n, in a construction of the contract of the property of the contract of the co					
LT & RT STA. 0+37 BK 1+30	736	552	0	552	143
TOTAL:	3,738	2,804	5,094	-2,291	7,120

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISH AND PLACE,6"
WETLAND AREAS	(C.Y.)	(C.Y.)	(C.Y.)	(C.Y.)	(S.Y.)
RAMP 4 INFIELD AREA	25,122	18,842	0	18,842	17,843
TOTAL:	25,122	18,842	0	18,842	17,843
GRAND TOTAL:	82,287	61,715	241,390	-179,675	151,106