

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
24	*	JOHNSON	150	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*(44-5, 6)RS, BSMART FY04-3				
98836				

PIPE UNDERDRAINS, 4"

LOCATION STATION TO STATION (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	PIPE UNDERDRAINS 4"		PIPE UNDERDRAINS 4" (SPECIAL)		CONCRETE HEADWALLS FOR PIPE DRAINS EACH	SHOULDER REMOVAL & REPLACEMENT 8" FOOT	COMMENTS
	FOOT		FOOT				
	LT.	RT.	LT.	RT.			
STA 275+00			12	16	2	14	
STA 280+00			12	16	2	14	
STA 285+00			12	16	2	14	
STA 290+00			12	16	2	14	
STA 295+00			12	16	2	14	
GAP EXISTING ROCK CUT							
303+75 TO 312+54 (MP 21.2)	879.0	879.0				1,758	
STA 305+50			20	28	4	14	SAG LOCATION
STA 309+00			9	13	2	14	
GAP EXISTING ROCK CUT							
318+00 TO 388+00 (MP 22.6)	7,000.0	7,000.0				14,000	
STA 318+00			12	16	2	14	
STA 320+00			12	16	2	14	
STA 325+00			12	16	2	14	
STA 330+00			12	16	2	14	
STA 335+00			12	16	2	14	
STA 340+00			12	16	2	14	
STA 345+00			12	16	2	14	
STA 350+00			12	16	2	14	
STA 355+00			12	16	2	14	
STA 360+00			12	16	2	14	
STA 365+00			12	16	2	14	
STA 370+00			12	16	2	14	
STA 375+00			12	16	2	14	
STA 380+00			12	16	2	14	
STA 385+00			12	16	2	14	
STA 388+00			12	16	2	14	CREST AT STA 386+00
GAP EXISTING ROCK CUT							
409+00 TO 423+00 (MP 23.2)	1,400.0	1,400.0				2,800	
STA 415+00			12	16	2	14	
STA 420+00			12	16	2	14	
STA 423+00			12	16	2	14	
GAP EXISTING ROCK CUT							
431+60 TO 457+44.50 (MP 23.9)	2,584.5	2,584.5				5,169	
STA 435+00			12	15	2	14	
STA 440+00			12	13	2	14	
STA 445+00			12	16	2	14	
STA 451+50			24	32	4	14	SAG LOCATION
STA 455+00			12	16	2	14	
EASTBOUND SUBTOTALS							
	43,616.9	40,577.7	1,229	1,589	200	85,403	
EASTBOUND TOTALS							
	84,195.0		2,818		200	85,403	
WB LANES							
STA 320+50 TO 323+90.9 (MP 13.3)	340.9	340.9				682	
STA 323+90			16	12	2	5	
323+91 TO 333+40.7 (MP 13.6)		949.8				950	US 45 INTERCHANGE (RAMP "A")
STA 326+50				12	1	5	
STA 330+00				12	1	5	
333+41 TO 335+82.5 (MP 13.7)		241.8				242	US 45 INTERCHANGE (RAMP "A")
STA 334+00				12	1	5	
335+82 TO 348+12.9 (MP 13.9)	1,230.4	1,230.4				2,461	US 45 INTERCHANGE
STA 336+50			16	12	2	14	
STA 341+00.0			32	24	4	14	SAG LOCATION
STA 345+00			16	12	2	14	
GAP STRUCTURE#044-0039							
349+99 TO 361+48.4 (MP 14.1)	1,149.0	1,149.0				2,298	US 45 INTERCHANGE
STA 350+00			16	12	2	14	
STA 353+50			16	12	2	14	
STA 359+00			16	12	2	14	
STA 361+48			16	12	2	14	
361+48 TO 362+85.2 (MP 14.1)	136.8	136.8				274	US 45 INTERCHANGE (RAMP "B")
362+85 TO 368+15.2 (MP 14.2)	530.0	530.0				1,060	US 45 INTERCHANGE (RAMP "B")

Fri Feb 6 14:05:48 2004
 C:\P\01\02\100202\0990202\202.m32 11v2-63