F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	JOHNSON	150	29
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

*(44-5,6)RS, BSMART FY04-3
98836

SHOULDERS

LOCATION STATION TO STATION	BITUMINOUS SURFACE REMOVAL 1"	PAVED SHOULDER REMOVAL *SEE NOTE 1*	BITUMINOUS SHOULDERS, SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE 8"	AGGREGATE SHOULDERS TYPE B	BITUMINOUS MATERIALS (PRIME COAT) *SEE NOTE 2*	SUB-BASE GRANULAR MATERIAL TYPE A, 4"	SHOULDER RUMBLE STRIP	REMARKS
	SQ YD	SQ YD	TON	SQ YD	TON	GALLONS	SQ YD	FOOT	
IL 146 INTERCHANGE									
RT 100 + 98 TO 23 + 50 RAMP A				607					WIDENING OF RAMP SHOULDER
RT 100 + 98 TO 10 + 65 RAMP A					2				STARTS ON IL 146
RT 10 + 65 TO 26 + 63 RAMP A			373		51	160			
RT 20 + 00 TO 22 + 50 RAMP A		56		56		5			FULL DEPTH PATCH (250 X 2)
RT 22 + 50 TO 22 + 60 RAMP A		7		7		1			FULL DEPTH PATCH (10 X 6)
RT 5 + 98 TO 10 + 10 RAMP B			96		13	41			
RT 7 + 67 TO 8 + 10 RAMP B		24		24		2			FULL DEPTH PATCH (43 X 5)
RT 8 + 45 TO 8 + 55 RAMP B		5		5		1			FULL DEPTH PATCH (10 X 4)
RT 10 + 10 TO 10 + 75 RAMP B			12		2	5			TRANSITION FROM 6' TO 10' SHOULDER
RT 10 + 75 TO 17 + 00 RAMP B			88		20	38			
RT 17 + 00 TO 19 + 41 RAMP B			56		8	24			
RT 19 + 41 TO 101 + 18 RAMP B					3				ENDS ON IL 146
RT 17 + 00 TO 101 + 18 RAMP B				150					WIDENING OF RAMP SHOULDER
RT 86 + 05 TO 20 + 00 RAMP C				440					WIDENING OF RAMP SHOULDER
RT 86 + 05 TO 10 + 60 RAMP C					2				
RT 10 + 60 TO 20 + 00 RAMP C			219		30	94			
RT 13 + 50 TO 17 + 20 RAMP C		124		124		11			FULL DEPTH PATCH (370 X 3)
RT 17 + 20 TO 20 + 17 RAMP C		66		66		6			FULL DEPTH PATCH (297 X 2)
RT 20 + 00 TO 25 + 30 RAMP C			74		17	32			
RT 25 + 30 TO 25 + 95 RAMP C			12		2	5			TRANSITION FROM 10' TO 6' SHOULDER
RT 25 + 95 TO 27 + 11.88 RAMP C			27		4	12			
RT 6 + 02 TO 10 + 10 RAMP D			95		13	41			
RT 10 + 10 TO 10 + 75 RAMP D			12		2	5			TRANSITION FROM 6' TO 10' SHOULDER
RT 10 + 75 TO 21 + 26 RAMP D			147		33	63			
RT 13 + 85 TO 16 + 00 RAMP D		48		48		4			FULL DEPTH PATCH (215 X 2)
LT 10 + 65 TO 22 + 26.19 RAMP A			108		37	46			
LT 9 + 90.36 TO 19 + 41 RAMP B			89		30	38			
LT 10 + 60 TO 25 + 49.99 RAMP C			139		47	60			
LT 10 + 01 TO 21 + 26 RAMP D			105		36	45			
MEDIAN CROSSOVER									
322 + 41 (MP 13.4)				355			355		
88 + 65.5 (MP 16.9)				355			355		
231 + 46 (MP 19.6)				355			355		
PROJECT TOTALS	17,471	2,551	40,743	5,817	8,050	20,776	1,065	219,361	

NOTE:
1) THE REQUIRED SAW CUTS FOR SHOULDER PATCHING SHALL BE INCLUDED IN THE COST PER SQ YD FOR PAVED SHOULDER REMOVAL AS PER SECTION 440 OF THE STANDARD SPECIFICATIONS.
2) FOR PROJECT TOTALS OF BITUMINOUS MATERIAL (PRIME COAT), SEE SURFACING SCHEDULE SHEETS # 33 - 34

Fri Feb 6 14:01:03 2004
c:\pr\projects\j90\j02\j90j02acd2.m32 LV-2-63