

F.A.P. RIE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	JOHNSON	150	36
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*(44-5,6)RS, BSMART FY04-3 98836				

BARRIER DELINEATION

LOCATION STA TO STA (MP IS THE LAST STA UNLESS OTHERWISE NOTED)	GUARDRAIL MARKERS, TYPE B		BARRIER WALL MARKERS, TYPE B		TERMINAL MARKERS DIRECT APPLIED EACH
	AMBER	CRYSTAL	AMBER	CRYSTAL	
	EACH	EACH	EACH	EACH	
FAI 24					
JOHNSON CO.					
EB LANES					
LT STA 345+91.85 TO STA 350+11 (MP 13.9)	4		2		1
RT STA 345+72.35 TO STA 350+50 (MP 13.9)		4		2	1
RT STA 404+93.35 TO STA 409+19 (MP 15.0)		4		2	1
LT STA 405+31.85 TO STA 409+19 (MP 15.0)	4		2		1
LT STA 415+32.85 TO STA 419+78 (MP 15.2)	4		2		1
RT STA 415+08.35 TO STA 419+78 (MP 15.2)		4		2	1
LT STA 439+76.35 TO STA 444+13 (MP 15.7)	4		2		1
RT STA 439+26.35 TO STA 444+13 (MP 15.7)		4		2	1
RT STA 469+89.35 TO STA 474+98.61 (MP 16.3)		4		3	1
LT STA 470+58.35 TO STA 474+98.61 (MP 16.3)	4		3		1
RT STA 101+92.19 TO STA 115+60.94 (MP 17.3)		8			1
RT STA 255+49.35 TO STA 259+44.29 (MP 20.1)		4		1	1
LT STA 255+60.85 TO STA 259+44.29 (MP 20.1)	4		1		1
RT STA 302+14.58 TO STA 309+70.83 (MP 21.1)		7			1
LT STA 301+39.58 TO STA 309+70.83 (MP 21.1)	6				1
WB LANES					
LT STA 348+17 TO STA 353+02.65 (MP 13.9)		4		2	1
RT STA 348+17 TO STA 352+83.15 (MP 13.9)	4		2		1
RT STA 408+05 TO STA 411+94.15 (MP 15.0)	4			2	1
LT STA 408+06 TO STA 412+31.65 (MP 15.0)		4	2		1
LT STA 417+83 TO STA 422+54.65 (MP 15.2)		4		2	1
RT STA 417+83 TO STA 422+10.65 (MP 15.2)	4		2		1
LT STA 442+40 TO STA 447+18.15 (MP 15.7)		4		2	1
RT STA 442+40 TO STA 446+93.15 (MP 15.7)	4		2		1
RT STA 473+62 TO STA 478+24.15 (MP 16.3)	4		3		1
LT STA 473+62 TO STA 478+83.65 (MP 16.3)		4		3	1
LT STA 109+46.83 TO STA 117+03.08 (MP 17.3)	6				1
RT STA 619+68 TO STA 623+58.15 (MP 20.1)	4			2	1
LT STA 619+68 TO STA 623+73.65 (MP 20.1)		4	2		1
RT STA 665+84.96 TO STA 672+53.71 (MP 21.1)	9				1
LT STA 665+90.30 TO STA 672+34.05 (MP 21.1)		7			1
LT STA 706+61 TO STA 707+61 (MP 21.8)					1
LT STA 411+41.38 TO STA 422+47.63 (MP 23.1)		7			1
PROJECT TOTAL		146		50	32

TEMPORARY RAMP

LOCATION STATION	TEMPORARY RAMP
	SQ YD
FAI 24	
EB LANES	
STA. 320+50	26.8
STA. 348+92.86	32.2
STA. 350+17.86	32.2
STA. 408+5.7	32.2
STA. 409+18.7	32.2
STA. 418+18.9	32.2
STA. 419+78.88	32.2
STA. 442+43.9	32.2
STA. 444+13	32.2
STA. 473+62.8	32.2
STA. 475+32.25	32.2
STA. 258+37.13	32.2
STA. 259+44.29	32.2
STA. 457+46	67.0
WB LANES	
STA. 320+50	26.8
STA. 348+17.89	32.2
STA. 349+67.14	32.2
STA. 408+5.7	32.2
STA. 409+18.7	32.2
STA. 417+88.9	32.2
STA. 419+42.26	32.2
STA. 442+40.13	32.2
STA. 444+18.33	32.2
STA. 473+99.9	32.2
STA. 475+32.25	32.2
STA. 619+68.69	32.2
STA. 620+84.19	32.2
STA. 457+46	67.0
U. S. 45 RAMP	
RAMP A	
STA. 11+9.54	17.8
STA. 1617+98.35 (U. S. 45)	17.8
STA. 1619+37.35 (U. S. 45)	17.8
RAMP B	
STA. 25+25.35	17.8
STA. 1617+89.68 (U. S. 45)	17.8
STA. 1619+44.67 (U. S. 45)	17.8
RAMP C	
STA. 11+50	17.7
RAMP D	
STA. 25+20	17.7
ILL 146 RAMP	
RAMP A	
STA. 10+65	35.6
RAMP B	
STA. 19+41	35.6
RAMP C	
STA. 11+60	35.6
RAMP D	
STA. 21+26	35.6
PROJECT TOTAL	1245

FILED: 6 MAR 2004
 COUNTY: JOHNSON
 PROJECT: 04-5,6 RS, BSMART FY04-3
 SHEET: 36 OF 36