F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	JOHNSON	150	38
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

*(44-5,6)RS, BSMART FY04-3
98836

TREE REMOVAL

LOCATION STA TO STA (MP IS THE LAST STA. UNLESS OTHERWISE NOTED)		OFFSET FROM E. P. FEET	TREE REMOVAL (6 TO 15 INCH) UNITS	TREE REMOVAL (OVER 15 INCH) UNITS	TREE REMOVAL ACRES ACRES	REMARKS
LT 282 + 52	MP(20.6)	92	9			WILLOW
LT 282 + 52	MP(20.6)	94	8 9			WILLOW
LT 282 + 52	MP(20.6)	97	6			WILLOW
LT 305 + 15	MP(21.0)	50	6			TREE WITHIN CLEAR ZONE - PERSIMMON
LT 306 + 30	MP(21.0)	130	6			1' UP FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 306 + 70	MP(21.0)	0 - 170			0.25	170' X 65' CENTERED ON CULVERT
LT 309 + 00	MP(21.1)	68	8			
LT 322 + 24	MP(21.3)	51	7 7 8			TREAT STUMP WITH HERBICIDE - WILLOW
LT 334 + 12	MP(21.6)	68	10			HAS FALLEN OVER PAVED DITCH
LT 353 + 50	MP(21.9)	40	7 6 6			TREAT STUMP WITH HERBICIDE - WILLOW
WB LANES						
RT 639 + 40	MP(20.5)	76	6			TREAT STUMP WITH HERBICIDE
RT 639 + 40	MP(20.5)	76	6			TREAT STUMP WITH HERBICIDE
RT 639 + 55	MP(20.5)	76	8			TREAT STUMP WITH HERBICIDE
RT 639 + 55	MP(20.5)	76	9			TREAT STUMP WITH HERBICIDE
RT 639 + 55	MP(20.5)	76	10			TREAT STUMP WITH HERBICIDE
RT 653 + 05	MP(20.8)	96	7			
RT 670 + 08	MP(21.0)	90		28		LAYING OVER PAVED DITCH
RT 707 + 07	MP(21.8)	36	8			TREAT STUMP WITH HERBICIDE
LT 321 + 98	MP(13.4)	47 - 100			0.02	53' X 10' CENTERED ON DITCH
LT 394 + 20	MP(14.7)	107	10 9 6 10			TREAT STUMP WITH HERBICIDE - WILLOW
LT 394 + 21	MP(14.7)	113	9			TREAT STUMP WITH HERBICIDE - SYCAMORE
LT 394 + 26	MP(14.7)	81	8			
LT 394 + 29	MP(14.7)	102	8 6			CEDAR
LT 394 + 30	MP(14.7)	101	7			CEDAR
LT 394 + 30	MP(14.7)	106	8			
LT 394 + 35	MP(14.7)	107	9			4' UP BACKSLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE - SYCAMORE
LT 407 + 75	MP(15.0)	95	8 9 10			TREAT STUMP WITH HERBICIDE - WILLOW
LT 407 + 83	MP(15.0)	91	13 7			TREAT STUMP WITH HERBICIDE - WILLOW
LT 418 + 36	MP(15.2)	190	6 9			TREAT STUMP WITH HERBICIDE
LT 418 + 39	MP(15.2)	183	6			TREAT STUMP WITH HERBICIDE
LT 418 + 40	MP(15.2)	181	15			TREAT STUMP WITH HERBICIDE
LT 418 + 50	MP(15.2)	190	11			TREAT STUMP WITH HERBICIDE
LT 419 + 80	MP(15.2)	75	9 7			TREE IS WITHIN CLEAR ZONE
LT 486 + 95	MP(16.5)	113	7			
LT 486 + 94	MP(16.5)	113	7			
LT 486 + 93	MP(16.5)	113	10			
LT 80 + 37	MP(16.8)	70 - 110			0.03	50' X 20' CENTERED ON CULVERT
LT 80 + 47	MP(16.8)	120	9			TREAT STUMP WITH HERBICIDE
LT 80 + 70 TO 81 + 40	MP(16.8)	110 - 140			0.04	20' CENTERED ON PAVED DITCH
LT 85 + 83	MP(16.9)	60	8			8' UP FORESLOPE OF PAVED DITCH - CEDAR
LT 87 + 10	MP(16.9)	40	8			8' UP FORESLOPE OF PAVED DITCH - CEDAR
LT 110 + 25	MP(17.3)	60 - 92			0.04	70' X 20' CENTERED ON CULVERT
LT 110 + 37	MP(17.3)	102	12			3' UP FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 110 + 81	MP(17.3)	100	8			FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 110 + 93	MP(17.3)	99	8			1' UP BACKSLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 109 + 54	MP(17.9)	58	10			
LT 159 + 50	MP(18.3)	60 - 110			0.03	50' X 20' CENTERED ON CULVERT
LT 618 + 47	MP(20.1)	40	12 13			6' UP BACKSLOPE OF PAVED DITCH
LT 619 + 93	MP(20.1)	50	11 11			5' UP FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 626 + 07	MP(20.2)	31	11			3' UP BACKSLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 626 + 10	MP(20.2)	31	7			8' UP BACKSLOPE OF PAVED DITCH
LT 635 + 03	MP(20.4)	100	7			1' UP FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 635 + 63	MP(20.4)	91	8			9' UP BACKSLOPE OF PAVED DITCH
LT 636 + 91	MP(20.4)	93	10			7' UP BACKSLOPE OF PAVED DITCH
LT 653 + 07	MP(20.8)	72	7 7 10			1' UP BACKSLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 657 + 15	MP(21.0)	116	7			WILLOW
LT 657 + 15	MP(21.0)	86	9			PINE
LT 657 + 16	MP(21.0)	66	10			
LT 666 + 05	MP(21.0)	74	9			
LT 666 + 05	MP(21.0)	60	6			
LT 684 + 61	MP(21.4)	60	7			TREAT STUMP WITH HERBICIDE
LT 684 + 69	MP(21.4)	60	7			TREAT STUMP WITH HERBICIDE
LT 684 + 71	MP(21.4)	60	7			TREAT STUMP WITH HERBICIDE
LT 415 + 50	MP(23.1)	101	13			
LT 415 + 53	MP(23.1)	99	7			
LT 417 + 82	MP(23.2)	65	8			MAPLE
LT 418 + 75	MP(23.2)	70	13			6' UP FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE - SWEET GUM
LT 418 + 93	MP(23.2)	68	6			3' UP FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE - SWEET GUM
LT 418 + 96	MP(23.2)	35	8			1' UP FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 419 + 06	MP(23.2)	68	6			4' UP FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE - SWEET GUM
LT 436 + 96	MP(23.5)	71	8			3' NORTH OF PAVED DITCH, 21' FROM MAIN PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 442 + 95	MP(23.6)	105	8			BACKSLOPE SIDE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 443 + 75	MP(23.6)	107	12			FORESLOPE SIDE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 444 + 38	MP(23.7)	115	8			FORESLOPE SIDE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
LT 444 + 96 TO 445 + 36	MP(23.7)	120 - 150			0.03	20' CENTERED ON PAVED DITCH
LT 445 + 40	MP(23.7)	64	10 10 10			
VIENNA/HARRISBURG (US 45) INTERCHANGE						
RT 16 + 81	RAMP A	50	10			5' UP FORESLOPE OF PAVED DITCH - TREAT STUMP WITH HERBICIDE
RT 24 + 03	RAMP B	59		19		10' FROM BEGINNING OF CONNECTING PAVED DITCH, ON SOUTH SIDE - TREAT STUMP WITH HERBICIDE
	PROJECT TOTAL		1,356	84	1.40	

NOTE:

1) TREES WITHIN 5' FROM ANY STRUCTURE ARE TO BE CUT DOWN AND IT'S STUMP TREATED WITH HERBICIDE OR AS DIRECTED BY THE ENGINEER.

2) TREE REMOVAL FIELD NOTES FROM PIPE CULVERT SURVEY DATED APRIL & MAY 2003. PAVED DITCH CONDITION SURVEY DATED MAY, JUNE, JULY & AUGUST 2003. CLEAR ZONE SURVEY DATED DECEMBER 2003.

Fri Feb 6 14:00:53 2004
g:\projects\H95202\H95202asc2.m32 LV-2-63