


DETAIL OF BITUMINOUS SIGN PADS



* LENGTH MAY BE INCREASED TO FIT FIELD CONDITIONS AND SATISFY THE MAXIMUM SLOPES AS DETAILED BELOW UPON APPROVAL BY THE ENGINEER.



SECTION A-A



SECTION B-B

ILLINOIS STANDARD

W8-I106

F. A. L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
24	*	JOHNSON	150	111
STA.		TO STA.		

* (44-5,6)RS, BSMART FY04-3 98836



COLORS:

LEGEND AND BORDER BACKGROUND BLACK NON-REFLECTORIZED ORANGE REFLECTORIZED

SIGN	DIMENSIONS							
SIZE	Α	В	C	D	Ε	F	G	Н
48X48	48.0	24.1	3,0	34.0	33.0	6.0	13.0	3.5

CTON		SERIES			BOR-		
SIGN							
SIZE	1	2	3	GIN	DER	STD.	
48X48	3 7C	7C	7C	0.8	1.2	B4-48D	

ALL DIMENSIONS IN INCHES

NOTE: PRIOR TO ALLOWING TRAFFIC ON ANY PORTION OF THE ROADWAY THAT HAS BEEN COLDMILLED, THE CONTRACTOR SHALL HAVE ERECTED "ROUGH GROOVED SURFACE" SIGNS THAT CONFORM TO THE ABOVE DETAILS. A MINIMUM OF ONE SIGN AT EACH END OF THE IMPROVEMENT WILL BE REQUIRED. THE CONTRACTOR SHALL MAINTAIN THE "ROUGH GROOVED SURFACE" SIGNS UNTIL THE COLDMILLED SURFACE IS COVERED WITH LEVELING BINDER OR SURFACE COURSE.

IF AT ANY TIME THE SIGNS ARE IN PLACE BUT NOT APPLICABLE, THEY SHALL BE TURNED FROM THE VIEW OF MOTORISTS OR COVERED AS DIRECTED BY THE ENGINEER.

THE COST OF FURNISHING, ERECTING, MAINTAINING, AND REMOVING THE REQUIRED SIGNS SHALL BE INCLUDED IN THE CONTRACT.



UNEVEN PAVEMENT SIGN



W8-11(48" x 48")

COLORS:

LEGEND AND BORDER - BLACK NON-REFLECTORIZED
BACKGROUND - ORANGE REFLECTORIZED

NOTE: PRIOR TO ALLOWING TRAFFIC ON ANY PORTION OF THE ROADWAY THAT HAS BEEN COLDMILLED OR BEFORE RESURFACING OPERATIONS BEGIN, THE CONTRACTOR SHALL HAVE ERECTED "UNEVEN PAVEMENT" SIGNS THAT CONFORM TO THE ABOVE DETAILS. A MINIMUM OF ONE SIGN AT EACH END OF THE IMPROVEMENT WILL BE REQUIRED. THE CONTRACTOR SHALL MAINTAIN THE "UNEVEN PAVEMENT" SIGNS UNTIL THE RESURFACING OPERATIONS ARE COMPLETED.

IF AT ANY TIME THE SIGNS ARE IN PLACE BUT NOT APPLICABLE, THEY SHALL BE TURNED FROM THE VIEW OF MOTORISTS OR COVERED AS DIRECTED BY THE FNGINFER.

THE COST OF FURNISHING, ERECTING, MAINTAINING, AND REMOVING THE REQUIRED SIGNS SHALL BE INCLUDED IN THE CONTRACT.

REVIS	REVISIONS				
DRAWN	2-15-89				
REVISED	4-6-93				
STD	9-41				