

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAI 57	*	ALEXANDER	17	3
FAP 726				
FED. ROAD DIST. NO. 7		BLANK	PROJECT	

*D-9 HOAN DETAIL REPAIR FY 04-01

98846

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: SFTY - 2A		100% STATE			
		UNIT	STRUCTURAL STEEL REPAIR QUANTITY (2 STRUCTURES)	JOINT REPLACEMENT QUANTITY (2 STRUCTURES)	TOTAL QUANTITY
50102400	CONCRETE REMOVAL	CU. YD.	-	12.9	12.9
50300160	NEOPRENE EXPANSION JOINT 4"	FOOT	-	93	93
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	-	12.9	12.9
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	50000	-	50000
50501110	STRUCTURAL STEEL REMOVAL	POUND	32600	-	32600
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	-	2230	2230
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO.	3.75	1.25	5
67100100	MOBILIZATION	L. SUM	0.75	0.25	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1.5	0.5	2
70400100	TEMPORARY CONCRETE BARRIER	FOOT	-	500	500
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	-	500	500
X0322556	STIFFENER INTERSECTION MODIFICATION	EACH	160	-	160
Z0002600	BAR SPLICERS	EACH	-	28	28
Δ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	-	2	2
Δ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	EACH	-	2	2

DESIGNED
CHECKED
DRAWN
CHECKED

Δ SFTY-3N